


15-163-02751-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County. Sec. 19 Twp. 9 Rge. 19 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NW NE NE
Lease Owner Nadel and Gussman
Lease Name Lambert Well No. 1
Office Address 1714 First National Bldg., Tulsa 3, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 1-4-19-58
Application for plugging filed 1-4-19-58
Application for plugging approved 1-4-19-58
Plugging commenced 1-4-19-58
Plugging completed 1-4-19-58
Reason for abandonment of well or producing formation Dry



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3620 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	206'	0
<p>RECEIVED STATE CORPORATION COMMISSION 1/13/58 JAN 13 1958 CONSERVATION DIVISION WICHITA, KANSAS</p>						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill hole with heavy mud from T.D. to 600' - set plug at 600'
with 20 sacks cement - filled hole with heavy mud ~~from~~ to 190'
set plug with 20 sacks cement - top plug at 40' with 10 sacks
cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Globe Cementing Company
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
L. C. Hay (employee of owner) ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Hay
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 8th day of January 19 58

My commission expires Nov. 3, 1960 _____ Notary Public.

PLUGGING
FILE NO. 19T 9 R 196
BOOK PAGE 79 LINE 27

15-163-02751-00-00

WELL LOG

Nadel and Gussman

Lambert No. 1

NW NE NE 19-9-19W
Rooks County, Kansas

Comm: 12-21-57
Comp: 12-30-57

Casing: 8-5/8" 206' w/125 sax

<u>Formations</u>	<u>Depth</u>
Sand, shells and shale	210
Shale and shells	750
Shale and sand streaks	1005
Sand	1250
Shale	1325
Red bed and shale	1523
Anhydrite	1565
Shale and shells	2075
Shale and lime streaks	2210
Shale and lime	3305
Lime	3535
Lime and shale	3620

RECEIVED
STATE CORPORATION COMMISSION
JAN 13 1958
CONSERVATION DIVISION
WICHITA, KANSAS

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

L. C. Hay, of lawful age, states that the above formations and depths are correct to his best knowledge and belief.

L. C. Hay

Subscribed and sworn to before me this 8th day of January, 1960.

Paul Brock
Notary Public

My commission expires Nov. 3, 1960

PLUGGING
FILE NO. 191 9 R19W
BOOK PAGE 74 LINE 27