


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. 24 Twp. 9 Rge. 19 (E) (W)
Location as "NE/CNW&SW" or footage from lines NE NE SE
Lease Owner MORGENSTERN & SPECTER
Lease Name MAYHEW Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 11-18-51 19
Application for plugging filed Nov. 2, 1961 19
Application for plugging approved Nov. 3, 1961 19
Plugging commenced November 27, 1961 19
Plugging completed December 2, 1961 19
Reason for abandonment of well or producing formation failure to produce profitably
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty Hays, Kansas
Producing formation Arbuckle Depth to top 3609 Bottom 3612 Total Depth of Well 3616 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	284ft.	none
				5 1/2" OD	3612'	2980 feet

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 3300 feet, Dumped 5 sacks Cement.
Circulated Mud at 550 feet, Pumped 20 sacks Cement.
Pumped 20 sacks cement at 200 feet, Set a rock-
-bridge at 40 feet.
Dumped ten sacks cement.

STATE CORPORATION COMMISSION
12/15/61
DEC 15 1961

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor LYNCH CASING PULLING COMPANY. NO. 457
Address R. Rt. 4 GREAT BEND, KANSAS

STATE OF Kansas COUNTY OF Russell, ss.
Morgenstern & Specter, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Morganstern
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of December, 19 61

My commission expires Dec. 1, 1964

Elsie Coady
Elsie Coady Notary Public.



WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-163-00419-00-00
COPY

Company- B & R DRILG. INC.
Farm- Mayhew No. 1

SEC. 24 T. 9 R. 19W
NE NE SE

Total Depth. 3616
Comm. 11-6-51 Comp. 11-18-51
Shot or Treated.
Contractor.
Issued. 1-26-52

County Books KANSAS



Elevation. 2199

Production. Pot. 116 bbls.

Figures indicate Bottom of Formations.

sand, shale	150
shale, shells	284
shale	610
shale, shells	700
sand	730
shale, shells	745
sand, shale	950
shale	1025
sand, shale	1315
shale, shells	1420
shale, red bed	1575
anhydrite	1610
shale, shells	1835
shale, lime	2125
shale broken, lime	2225
lime, shale	2420
shale, lime brkn	2505
shale, lime	3195
lime brkn, shale	3255
lime, shale	3461
lime	3565
lime, shale	3613
drill pipe corr.	3616
Total Depth	

Tops:	
Heebner	3329
Kansas City	3369
Base-Kansas City	3530
Congl. Shale	3589
Reworked Arb.	3605
Arbuckle	3609

2201
1575
126

RECEIVED
STATE GEOLOGICAL COMMISSION
NOV 1 1961
CONSERVATION DIVISION
Wichita, Kansas