

15-163-03048-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-7-31-48

LEASE NAME Jelinek

WELL NUMBER 3

2310 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 24 TWP. 9 RGE. 19 (E or W)

COUNTY Rooks

Date Well Completed: \_\_\_\_\_

Plugging Commenced July 1, 1987

Plugging Completed July 1, 1987

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Bowman Oil Company

ADDRESS P. O. Box 37 Codell, Ks 67630

PHONE# (913) 434-2304 OPERATORS LICENSE NO. 6931

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on July 1, 1987 (date)

by Dennis L. Hamel (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? Yes

Producing Formation Arbuckle Depth to Top 3579 Bottom 3583 T.D. 3583

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle		0	265	8 5/8	265	None
3578-83	Water & oil	0	3568	5 1/2	3568	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Perforated 3192, 1570, 270 and cemented well from bottom to top with  
200 sacks 65/35 poz, 10% jel, 2% lite with 1/4# flo-cel and 8 sacks of  
balls, shut in at 300#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. \_\_\_\_\_

Address Russell, Kansas 67665

STATE OF Kansas COUNTY OF Rooks, ss.

Louis D. Bowman (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Louis D. Bowman

(Address) 101 Petroleum Codell, Ks 67630

SUBSCRIBED AND SWORN TO before me this 23 day of September, 19 87

Vesta J. Russell  
Notary Public

My Commission Expires: July 17, 1988



SEP 25 1987  
9/25/87  
CONSERVATION DIVISION

# K. G. S. LIBRARY


9 19W  
**COPY**

Company - **DERBY OIL COMPANY**  
Farm - **Jelinek** No. 3

SEC. 24 NW SW SW

Total Depth. 3582' P.B. 3580'  
Comm. 7-31-48 Comp. 9-2-48  
Shot or Treated. Acidized  
Contractor. G. W. Peel  
Issued. 12-4-48

County. Rooks  
KANSAS



CASING:  
3-5/8" 265' Cem. w/125 Sx.  
5-1/2" 3568' Cem. w/100 Sx.

Elevation. 2155' KB

Production. Pot. 126BO, no wtr.

Figures Indicate Bottom of Formations.

sand & shale	265
shale & shells	1020
sand & shale	1300
shale	1530
anhydrite	1565
red bed	1710
shale & shells	1885
lime & shale	2440
lime	2775
lime & shale	3157
????	3213
lime	3571
arbuckle	3579
dolomite	3582
Total Depth	

Plugged back to 3580'

**Geological Data:**

Lansing 3331 show oil 3492-3503  
Arbuckle 3567 good show of oil

Drilled cement, folat & shoe to 3571'.  
Drilled deeper to 3575'. Bailed out &  
tested 1 1/2 BOPH. Drilled to 3578'. Bailed  
& tested. No increase. Acid. w/500 gals.  
Rigged swab. Lost swab in hole. Fished out  
swab. Swabbed down & test 4 BOPH for 7 hrs.  
Acid. w/1000 gals. Took acid on vacuum, swabbed  
down & tested 4 BOPH 8 hrs. Drilled down to  
3579' & tested 4 BOPH. Drilled to 3585' &  
tested 5 BOPH 4 hrs. Drilled to 3589' &  
tested 4.8 BOPH 10 hrs. Ran tubing. Acid.  
w/1000 gals. @ 3583-89 w/Dowell pilot. Pulled  
tubing. Swabbed 1500' off bottom, mostly wtr.  
Swab test 5 1/2 BO 75 BW in 3h4s. Plugged back  
to 3582 1/2 w/1 Sx. calseal. Swabbed down 200'  
off bottom. Bottom wtr broke in. Ran 26 gal.  
plastic. Plugged back to 2580. Wtr shot off.  
Ran 3540' tubing & 140 rods. State Pot. 126  
BO, no wtr, 24 hrs. (5.66 BOPH.)

RECEIVED  
STATE CORPORATION COMMISSION

SEP 25 1987

CONSERVATION DIVISION  
Wichita, Kansas