


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Reeks County. Sec. 17 Twp. 9S Rge. 19 (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines NW NW SE
Lease Owner PETROLEUM, INC.
Lease Name Gregg Well No. 1
Office Address 100 Derby Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 6/7 1949
Application for plugging filed 6/7 1949
Application for plugging approved 6/7 1949
Plugging commenced 6/7 1949
Plugging completed 6/7 1949
Reason for abandonment of well or producing formation



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough, Box 207, Great Bend, Ks.
Producing formation Depth to top Bottom Total Depth of Well 3625 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	194'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 195'. Placed plug at 195' - placed 15 sacks cement on plug. Filled hole with mud to 30'. Placed plug at 30'. Filled hole with 10 sacks cement to top of hole.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to PETROLEUM, INC.
Address 100 Derby Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Eric H. Jager (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Eric H. Jager
100 Derby Building, Wichita 2, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 7 day of June, 1949
Raymond Koch Notary Public.

My commission expires June 7, 1952.

22-5133-s 9-48-10M

PLUGGING
FILE SEC 17 T 9 R 19 S
BOOK PAGE 106 LINE 9

6/15/49

WELL LOG GREGG NO. 1

Lease Owners: PETROLEUM, INC. Sec. 17, Twp. 9S, Range 19W
 Contractor: Drillers, Inc. Location: NW NW SE
 Total Depth: 3625' County: Rooks - Kansas
 Commenced: May 27, 1949 Elevation: 2087 D.F.
 Completed: June 7, 1949 P roduction: Dry Hole
 Casing: 194' of 8 5/8"

Figures below indicate bottom of formation:

45	Surface soil
195	shale, lime & shells
295	Shale
560	shale & shells
620	red bed
830	sandy shale
980	shale & sand
1225	sand
1255	shale
1497	red bed rock
1538	Anhydrite
2025	shale
2130	lime & shale
2240	shale
2265	sand
2395	shale
2530	lime & shale
2550	shale
2595	lime
2760	lime & shale
2870	shale
3005	lime & shale
3059	shale
3120	lime
3255	lime & shale
3564	lime
3613	Conglomerate
3625	lime
3625	TOTAL DEPTH

I hereby certify that this is a true and correct log of the abovementioned well.

PETROLEUM, INC.

Eric H. Jager
 Eric H. Jager

STATE OF KANSAS
 SS.
 SEDGWICK COUNTY

Subscribed and sworn to before me, a Notary Public in said County and State this 14th day of June, 1949.

Rosamond Koch
 Notary Public

My Commission expires: June 7, 1952.

