


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rooks County. Sec. 24 Twp. 9 Rge. 19 (X) W (W)

Location as "NE/CNW/SW" or footage from lines _____
Lease Owner Raymond Oil Company, Inc.
Lease Name Mayhew Well No. 1
Office Address 410 Fourth National Bank Bldg. Wichita Kans.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed September 23 1963
Application for plugging filed May 26 1964
Application for plugging approved June 3 1964
Plugging commenced June 8 1964
Plugging completed June 10 1964
Reason for abandonment of well or producing formation No longer commercially productive
If a producing well is abandoned, date of last production June 2 1964
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well E. Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3650 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	230'	
				5 1/2"	3639	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped 4 Sx. Portland Cement on top of chat fill back, with dump baler.
Pulled 5 1/2 up to 550 ft. Pumped Mudthrough 5 1/2 casing untill mud circulated
Pumped 20 Sx. cement to 550 ft. Pulled pipe up to 200ft., pumped 20 Sx. cement to 200 ft. pulled remaining pipe and pumped 10 sx. cement in top of surface pipe.

RECEIVED
STATE CORPORATION COMMISSION
6/29/64
JUN 29 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bert Self Casing Pulling Co. # 48
Address R.R. #4 Hutchinson Kansas

STATE OF Kansas, COUNTY OF Reno, ss.

_____, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Self
R.R. #4 Hutch. Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 25 day of June, 1964

My commission expires October 18, 1965
Notary Public.

RAYMOND OIL COMPANY, INC.
 NO. 1 MAYHEW
 W/2'NE SE 24-9S-19W'
 Rooks County, Kansas
 MAYHEW PROSPECT

15-163-19331-00-00

ELEVATION: 2202 KB
 2200 DF
 2197 GL

Contractor: Raymond Oil Company, Inc. - Rig #9
 Commenced: September 14, 1963
 Completed: September 23, 1963 (Rotary)

Casing Record:
 8 5/8" @ 230' w/95 sx
 5 1/2" @ 3639' w/100 sx

Figures Indicate Bottom of Formation

<u>Formation</u>	<u>Depth</u>
Shale	1055
Sand	1300
Shale - Red Bed	1576
Anhydrite	1615
Red Bed - Shale	1769
Shale & Shells	2055
Lime & Shale	2494
Shale & Lime	2615
Lime & Shale	2770
Shale & Lime	3000
Lime & Shale	3340
Lime	3449
Lime & Shale	3489
Lime	3566
Lime & Shale	3623
Arbuckle	3637
Lime	3648
Lime & Shale	3650
Rotary Total Depth	3650

RECEIVED
 STATE CORPORATION COMMISSION

JUN 3 1964

CONSERVATION DIVISION
 Wichita, Kansas

TOPS:

	<u>Sample</u>	<u>Electric Log</u>
Anhydrite	1576 Driller	1580
Topeka	3132	3134
Heebner	3343	3345
Toronto	3363	3365
Lansing	3383	3387
Base Kansas City	3590	3592
Arbuckle	3623	3624
Rotary Total Depth	3650	3652

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I hereby certify that the above is true and correct to the best of my knowledge.

Wm. M. Raymond
 Wm. M. Raymond, President
 RAYMOND OIL COMPANY, INC.

Subscribed and sworn to before me this 18th day of October, 1963.

Bernice Baldt
 Notary Public

My commission expires

December 10, 1966

