


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plugging
off formations.



Locate well correctly on above
Section Plat

ROOKS County. Sec. 18 Twp. 9S Rge. 19 (E) (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. SW 1/4 NE 1/4 NW 1/4
Lease Owner Aylward Drilling Co. et al.
Lease Name Marcotte "B" Well No. 1
Office Address 813 First Natl. Bank Bldg. Wichita, 2, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed May 27th 19 49
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced May 27th 19 49
Plugging completed May 27th 19 49
Reason for abandonment of well or producing formation Dry
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Lester R. Betty, Great Bend, Kansas.
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	159'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom Bridge build at 173' from top of Rotary table of tree limbs, sacks, hulls and rock, top of bridge 165' from top of rotary table, 15 sacks of cement on top of bridge. Top bridge 40' from top of rotary table to 35' from top of table, held Kelley, then filled to top of surface pipe 4' below ground level with cement; drilling nipple screwed out 4' from surface or ground level.

RECEIVED
Conservation Div.
6/14/49
JUN - 4 1949
STATE CORPORATION
COMMISSION
KANSAS

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Aylward Drilling Company
Address 813 First National Bank Building, Wichita, 2, Kansas.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
N. W. Aylward (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) N W Aylward
410 East Fourth, Hoisington, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of June 19 49
My commission expires July 9, 1952.

Alfred F. Shalshy
Notary Public.

22-2025 2-48-15M
PLUGGING
FILE SEC 18 T 9 R 19
BOOK PAGE 99 LINE 30

MARGOTTE "B" #1

Casing Record:
8" - 159'

COMPANY: Aylward Drilling Co. and
The Derby Oil Co.
CONTRACTOR: Aylward Drilling Co.

Location:
SW/4 NE/4 NW/4 of
Sec. 18-98-19W,
Rooks Co., Kansas

COMMENCED: May 18, 1949
COMPLETED: May 27, 1949

Elevation: 2063 D.F.
Potential: B & A

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface	0	4	
Brown Clay	4	25	
Shale, blue	25	60	
Sandy grey clay	60	100	
Blue shale	100	162	
Shale	162	385	Set 8" Casing and cemented with 90 sax.
Sand	385	520	
Shale with sand streaks	520	930	
Shale and sand	930	985	
Sand	985	1220	
Shale and red bed	1220	1450	
Shale and shells	1450	1500	
Anhydrite	1500	1540	
Shale	1540	1545	
Shale and shells	1545	1950	
Lime and shale	1950	2084	
Lime	2084	2100	
Lime and shale	2100	2340	
Lime	2340	2365	
Lime and shale	2365	2380	
Shale	2380	2405	
Lime	2405	2410	
Lime and shale	2410	2510	
Lime	2510	2530	
Shale	2530	2545	
Lime and shale	2545	2830	
Shale	2830	2860	
Lime	2860	2870	
Shale	2870	2903	
Lime and shale	2903	3095	
Lime	3095	3110	
Lime, soft	3110	3135	
Lime	3135	3174	
Lime and shale	3174	3284	
Lime	3284	3322	
Lime and shale	3322	3375	
Lime, soft	3375	3400	
Lime	3400	3544	
Shaly Conglomerate	3544	3548	
Cherty Conglomerate	3548	3575	

RECORDED
JUN - 4 1949
STATE CORPORATION
COMMISSION
KANSAS

T.D. 3575'

<u>Formation Tops</u>	
Topeka	3046
Keokuk	3253
Lansing	3291
Base K.C.	3504
Shaly Conglomerate	3544
Cherty Conglomerate	3548

PLUGGING
FILE SEC 18 T 9 R 19W
BOOK PAGE 99 LINE 30

I certify that this is a true and correct copy of the above log to the best of my knowledge.

Al Skalsky
Al Skalsky

Subscribed and sworn to before me this 1st day of June, 1949.

Florence Cooper
Notary Public

My Commission Expires;
July 16, 1952