


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. 18 Twp. 9S Rge. (E) 19(W)
Location as "NE/CNW¹/₄SW¹/₄" or footage from line 330' from E & 2310' from N
Lease Owner Continental Oil Company Lines
Lease Name H. M. Whisman Well No. 1
Office Address Drawer 1267, Ponca City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 19, 19 51
Application for plugging filed June 19, 19 51
Application for plugging approved June 23, 19 51
Plugging commenced June 21, 19 51
Plugging completed June 21, 19 51
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes - telephone

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation Arbuckle Depth to top 3642' Bottom 3700' Total Depth of Well 3700' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	Dry	3642'	3700'	10 3/4"	201'4"	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 210'; set plug at 210' and cemented with 20 sacks; filled hole with heavy mud to 35'; set plug at 35' and capped with 10 sacks cement. Plugged and abandoned 6/21/51.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to F. L. Dunn
Address R. F. D. #4 Lyons, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
F. L. Dunn (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

FLD-AEA State Corp. Comm. (Signature) F. L. Dunn

File Globe Oil & Ref. Co. R. F. D. #4 Lyons, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 20th day of July, 19 51

Nat'l. Coop. Ref. Assn. J. C. Fitzgerald Notary Public.

My commission expires Dec. 30, 1953

23-5091-s 8-50-10M

PLUGGING
FILE SEC 18 T 9 R 190
BOOK PAGE 90 LINE 9

RECEIVED
7/24/51
24 1951

15-163-00407-0000

NEW WELL COMPLETION AND/OR ABANDONMENT RECORD

A. F. E. No. 5 11 1135

1 Dist. West Kansas Field St Barry Lease H. H. Whisman Well No. 1
 2 Co. Rock State Kansas Contractor Anschutz Drilling Co., Inc. T.D. 3700' P.D. _____ ft.
 3 Landing Flange Elev. 2005' ft. Depth Measured From HT; Height of Measuring Point from Landing Flange 4' ft.
 4 Date: Spudded 6/10/51 Drilling Completed 6/20/51 Tested 6/21/51 Rig Released _____

CASING, LINER AND TUBING RECORD

SIZE O. D. IN.	WT. LB./FT.	THREADS NO. & TYPE	GRADE AND MAKE	NEW OR S. H.	E. L. L. W. SMLS.	DEPTH SET FT.	MEASUREMENTS INC. THREADS			TOP OF LINER	NO. OF JOINTS	HOLE SIZE
							QUANTITY SET	QUANTITY PULLED	QUANTITY LEFT IN HOLE			
10 3/4	40	8-V		SH	LS	189'	201'4"	None	201'4"		10	

CEMENTING RECORD

METHOD	MAKE AND TYPE CEMENT	SACKS USED	SQUEEZED AWAY	NO. OF BATCHES	FINAL PRESSURE	SLURRY WT. LB./GAL.	HOURS SET	DEPTH		REMARKS: TEMP. CALIPER, OTHER LOGS
								FROM	TO	
Howey	Portland	1:5		1		15	*	0	125'	Surface casing
Dump	Portland	20		1		-	*	-	210'	Plugging
Dump	Portland	10		1		-	*	-	35'	Plugging

ACIDIZATION AND SHOT RECORD

DATE	PRODUCTION OR P. I.		HOW TEST MADE	GAL. ACID	SHOT QTS.	DEPTH		NAME OF ZONE	TYPE FORMATION	REMARKS
	BEFORE	AFTER				FROM	TO			
None										

SECTION PERFORATED

NAME OF PAY	DEPTH		SIZE OF HOLE	HOLES PER FOOT	DATE	SERVICE CO. OR TYPE SLOTS	REMARKS
	FROM	TO					
None							

PRODUCING EQUIPMENT

29 RODS: Number None Size _____ in., Number _____ Size _____ in., Total Singles _____ Length _____ ft.
 30 PUMP: Size None Plunger Diam. _____ Make _____ Type _____
 31 PUMPING UNIT: Make None Type _____ Stroke _____ in. @ _____ SPM; Beam Capacity _____ lb.
 32 Torque @ 20 SPM _____ in. lbs.; Gear Box _____ H.P., Prime Mover Make _____
 33 H.P. @ _____ RPM. Other Remarks _____
 34 GAS ANCHOR None
 35 OTHER LIFT EQUIPMENT None
 36 _____
 37 PACKER: Set at None ft. Make _____ { ALSO SEE SKETCH }
{ ON REVERSE SIDE }

PRODUCING STRATA

NAME	TOP	BASE	POROSITY %	PERM. MD.	NET THICKNESS FT.	REMARKS: STATE CONTENTS OF ALL PRODUCING STRATA, O. G. & W. GIVING FLUID CONTACTS, D. S. T., ETC.
Arbuckle	3642'	3700'			-	Dry

REMARKS: Drilled to 3502'; took drill stem test from 3482' to 3502'; tool opened 45 min.; recovered 3' of drilling mud; deepened to 3700'; ran electrical survey; no commercial show of oil was encountered; filled hole with heavy mud to 210'; set plug at 210' and cemented with 20 sacks; filled hole with heavy mud to 35'; set plug at 35' and cased with 10 sacks; plugged and abandoned 6/21/51.

50 Located: 330' from the East and 2310' from the North lines of Sec. 10, T9S, R19W, Rock County, Kansas.

53 Material left in the hole cleared on HT #37051.

56 Estimate Total Cost \$ 20,763.00 Conoco Interest 100 % Operated by Continental Oil Company
 57 Potential Dry b/d/Mcf/d @ _____ #TP and #CP on _____ Hr. Test Meas. Est. Allowable Dry b/d
 58 Other Production or Well Test Results _____

60 Signed [Signature] District Superintendent
 61 Signed _____ Division Superintendent
 62 Signed _____ Region Manager
 63 Signed [Signature] Well Engineer
 64 Prepared by A. E. Anderson Date 6/21/51

PLUGGING
 FILE SEC 10 T 9 R 19W
 BOOK PAGE 90 LINE 9

DISTRIBUTED TO
 Mgr. P. & D. [Signature] Acct'g [Signature]
 Region TCD District FLD
 Others: State Corp. Comm. _____
 Globe Oil & Ref. Co. _____
 Nat'l. Coop. Ref. Assn. _____

15-163-00407-0000

CONTINENTAL OIL COMPANY

#1 Whisman SE SE NE 18-9-19
Rooks County, Kansas

0	40	Sand & post rock
40	192	Shale & shells
192	315	Shale
315	750	Shale & red bed
750	800	Sand
800	940	Shale & shells
940	990	Shale
990	1180	Sand
1180	1475	Red bed & shale
1475	1505	Red bed & shale
1505	1542	Anhydrite
1542	1653	Shale & shells
1653	1885	Shale & shells
1885	2105	Shale & shells
2105	2270	Shale & lime
2270	2390	Shale & lime
2390	2540	Shale
2540	2630	Shale & lime
2630	2720	Shale & lime
2720	2810	Lime & shale
2810	2910	Shale
2910	3000	Shale & lime
3000	3130	Sandy shale
3130	3215	Shale & lime
3215	3270	Lime
3270	3335	Lime & shale
3335	3375	Lime & shale
3375	3430	Lime
3430	3475	Lime
3475	3505	Lime
3505	3570	Lime & shale
3570	3642	Shale, lime & chert
3642	3645	Congl.
3645	3703	Arb
3703		Total Depth
		D&A

COMMENCED: 6/8/51
COMPLETED: 6/21/51

ELEV: 2085'

TOPS:
Anhy 1505
Topeka 3067
Heeb 3274
Toronto 3293
Lensing 3314
Congl 3565
Arb 3642

CASING RECORD
Set 10-3/4" surface pipe
at 187' with 125 sacks
cement.

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the #1 Whisman located SE SE NE 18-9-19W, Rooks County, Kansas.

ANSCHUTZ DRILLING COMPANY, INC.

By: *H. R. Jensen*

Subscribed and sworn to before me this 28th day of June, 1951.

Patricia Neep
Notary Public

My commission expires January 21, 1954.

PLUGGING
FILE SEC 18 T 9 N 19 W
BOOK PAGE 90 LINE 9

RECEIVED
STATE CORPORATION COMMISSION
JUL - 6 1951
CONSERVATION DIVISION
Wichita, Kansas