

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Rooks County, Sec. 18 Twp. 9 Rge. 19 (E) (W) X

Location as "NE/CNW&SW&SE" or footage from lines. SW/SW/SE
Lease Owner Kathol Petroleum, Inc.
Lease Name Rempe
Office Address P. O. Box 532, Great Bend, Kansas 67530 Well No. 1
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 4-10-72 19
Plugging completed 4-20-72 19
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 3579 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	207	None
				5 1/2	3548	818.73'

RECEIVED
STATE CORPORATION COMMISSION
4/25/72
APR 25 1972
CONSERVATION DIVISION
Wichita, Kansas


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed a plug to 3200'. Dumped 30' sand and 5 sacks cement. Shot casing at 2917'. Spotted oil. Shot casing at 2416, 1913, 1432 and 804 ft. Laid down a total of 25' of 5 1/2" casing. Sun squeezed well with 5 sacks hulls, 28 sacks gel, and 120 sacks 50/50 Pozmix with 6% gel.

Name of Plugging Contractor Rockhold Engineering, Inc.
Address P. O. Box 698, Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss. James W. Rockhold

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well on file and that the same are true and correct. So help me God.



(Signature) James W. Rockhold James W. Rockhold
P. O. Box 698, Great Bend, Kansas 67530

Subscribed and Sworn to before me this 21st day of April, 1972

Cathy Miller
Cathy Miller Notary Public

My commission expires September 30, 1975

DRILLERS LOG

15-163-20203-0000

No. 1 REMPE

CASING RECORD: COMPANY: Kathol Petroleum, Inc. DESCRIPTION:
 8 5/8" @ 207' w/ 145 sacks cem. CONTRACTOR: Kathol Petroleum, Inc. Approx. SW SW SE
 5 1/2" @ 3548' w/ 150 sacks cem. COMMENCED: April 26, 1969 Sec. 18-9S-19W
 Rooks Co., Kansas
 COMPLETED: May 6, 1969 ELEVATION:
 2075' K.B.
 TOTAL DEPTH: 3550' I.P. State Test 60 BOPD
 D.D. 3579'

FORMATION:	FROM	TO	REMARKS
surface soil	0	207	
shale & red bed	207	740	
sand	740	800	
sand & shale	800	1200	
red bed & shale	1200	1484	
anhydrite	1484	1525	
shale	1525	1740	
shale & shells	1740	2115	
shale & lime	2115	2375	
shale & lime	2375	3125	
lime & shale	3125	3205	
lime & shale	3205	3275	
lime	3275	3550	R.T.D.

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 13 1972
 CONSERVATION DIVISION
 Wichita, Kansas

Drilled Deeper:

dolomite 3550 3579 T.D.

I hereby certify that the above information is true and correct to the best of my knowledge.

KATHOL PETROLEUM, INC.

Don D. Shawver
 Don D. Shawver

Subscribed and sworn to before me this 23rd day of June, 1969.

Betty M. Maloney
 Betty M. Maloney, Notary Public

My Commission Expires:

