

15-163-21363-0000

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Rooks SEC. 18 TWP. 9S RGE. 19W E/W  
 Location as in quarters or footage from lines:  
C S/2 SW/4 NW/4


Lease Owner Frontier Oil Company  
 Lease Name Baldwin Well No. 1  
 Office Address 1720 KSB Building, Wichita, Kansas 67202  
 Character of Well (Completed as Oil, Gas or Dry Hole): D & A  
 Date Well Completed August 7, 1981  
 Application for plugging filed August 7, 1981  
 Plugging commenced August 7, 1981  
 Plugging completed August 7, 1981  
 Reason for abandonment of well or producing formation D & A

Locate Well  
 correctly on above  
 Section Platt.

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 3,581'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	255.53'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Plugged hole @ 850' w/70 sx cement  
@ 240' w/30 sx cement  
@ 40' w/10 sx cement  
50-50 Pozmix, 4% Gel, 3% C.C.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Red Tiger Drilling Company  
1720 KSB Building, Wichita, Kansas 67202


STATE OF Kansas COUNTY OF Sedgwick, ss.  
Gloria Fawcett (employee of owner) ~~owner or operator~~ of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) Gloria Fawcett  
1720 KSB Building, Wichita, Ks.  
 (Address)

SUBSCRIBED AND SWORN TO before me this 11th day of August, 19 81.

My Commission expires: \_\_\_\_\_

*Joyce A. Baer*  
 RECEIVED  
 STATE CORPORATION COMMISSION  
 8/12/81  
 AUG 12 1981  
 CONSERVATION DIVISION  
 Wichita, Kansas





Operator **Frontier Oil Company** DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:  
Dry Hole

Well No. **1** Lease Name **Baldwin**


S 18 T 9S R 19 <sup>E</sup>/<sub>W</sub>

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries. SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface Clay & Shale	0	266		
Shale	266	940		
Sand	940	1215		
Shale & Sand	1215	1491		
Anhydrite	1491	1533		
Shale	1533	1710		
Shale & Lime	1710	2000		
Shale	2000	2085		
Lime & Shale	2085	2145		
Shale & Red Bed	2145	2235		
Shale	2235	2580		
Shale & Lime	2580	2785		
Lime	2785	3510		
Lime & Chert	3510	3550		
Lime	3550	3581		
RTD		3581		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<div style="text-align: right; margin-bottom: 10px;">             _____            Signature         </div> <div style="text-align: right; margin-bottom: 10px;">           _____            Title         </div> <div style="text-align: right;">           _____            8-11-81            Date         </div>
---------------	--