


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

## WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Rooks County, Sec. 33 Twp. 9 Rge. (E) 17(W)  
Location as "NE/CNW/SW" or footage from lines C NW  
Lease Owner Leben Drilling, Inc.  
Lease Name Westhusin Well No. 1  
Office Address Box 486, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed August 17 19 71  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced August 24 19 71  
Plugging completed August 27 19 71  
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3578 Feet  
Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	209'	8 5/8"	209'	none
			3576'	5 1/2"	3576'	1576.81' yellow 1145.66' black

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded back to 3570'. Set plug at 3200' and dumped 5 sacks of cement.

Pumped in 20 sacks gel mud with 3 sacks hulls, 70 sacks pos mix 6% gel, 8 sacks gel and 50 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 16 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor PIPE PULLERS, INC. (If additional description is necessary, use BACK of this sheet)  
Address Box 486, Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Evelyn Roth

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth  
Ellinwood, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of September, 19 71

My commission expires Feb. 10, 1975

George A. Meyer  
Notary Public.

DRILLER'S LOG

COMPANY  
CONTRACTOR  
FAHM  
LOCATION

TILCO, ET AL  
LEBEN DRILLING, INC.  
WESTHUSIN #1  
C NW SECTION 33-93-17W  
ROOKS COUNTY, KANAS  
9-26-69  
10-3-69

COMMENCED  
COMPLETED

0 65  
65 185  
185 209  
209 425  
425 775  
775 1035  
1035 1350  
1350 1387  
1387 1840  
1840 3010  
3010 3578  
3578

Clay, Sand, Post Rock  
Sand, Shale, Blue Shale  
Blue Shale  
Shale, Shells  
Shale, Red Bed  
Sand, Shale  
Red Bed  
Anhydrite  
Shale  
Lime, Shale  
Lime  
RTD

RECEIVED  
STATE CORPORATION COMMISSION  
8-18-71  
AUG 18 1971  
CONSERVATION DIVISION  
Wichita, Kansas

8 5/8" 20# new surface casing set @ 209' cemented with 160 sacks common cement,  
2% cc.

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct  
copy of the log of the Westhusin #1 Well, located C NW of Section 33, Township 9  
South, Range 17 West of Rooks County, Kansas, as reflected by the records of  
Leben Drilling, Inc.

Leslie Kite  
Leslie Kite

STATE OF KANSAS )  
COUNTY OF BARTON ) ss

Subscribed and sworn to and before me, a Notary Public, in and for  
Barton County, Kansas, this 14th day of October, 1969.



Ulanda Nichols  
Ulanda Nichols