

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. 11 Twp. 9S Rge. (E) 19 (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. NE 1/4 NW 1/4 SE 1/4
Lease Owner. The Aylward Production Co. et al.
Lease Name. Ruder Well No. 1
Office Address. 813 First Natl. Bank Bldg. Wichita, 2, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole). Dry
Date well completed. June 2, 1946 19
Application for plugging filed. June 4, 1946 19
Application for plugging approved. June 8, 1946 19
Plugging commenced. June 8, 1946 19
Plugging completed. June 12, 1946 19
Reason for abandonment of well or producing formation.

If a producing well is abandoned, date of last production. 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well.
Producing formation. Depth to top. Bottom. Total Depth of Well. 3605 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	293'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with heavy mud by rotary pump
Circulated every 500'
Set crushed rock bridge at 275', dumped
25 sacks cement on bridge
Set bridge of crushed rock at 25', filled
with cement to cellar.

11 9 1946
57 13

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Aylward Production Company
Address 813 First Natl. Bank Bldg., Wichita, 2, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
J. W. Hummel (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God.

(Signature) J. W. Hummel OCT 9 1946
(Address)

SUBSCRIBED AND SWORN to before me this 8th day of October 1946

My commission expires January 19, 1947.

Notary Public

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

RECEIVED
JUL 6 - 1946
RECEIVED


15-163-02899-00-03

Company - AYLWARD PROD. CO., ET AL
Farm - Ruder No. 1.

SEC. 11 T. 9 R. 19 W
NE NW SE

Total Depth. 3605
Comm. 5-23-46 Comp. 6-2-46
Shot or Treated.
Contractor. Aylward Drlg. Co.
Issued. 7-6-46

County. Rocks
KANSAS



CASING:
8 5/8" 293' Cem.

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

surface clay & shale	40
clay & sand	90
shale	445
sand	505
shale	685
sand	745
shale & shells	930
sand	1050
shale	1190
lime	1235
red bed	1310
sand	1340
shale	1440
anhydrite lime	1475
red rock	1590
shale	1785
salt	1890
shale & shells	2490
lime	2510
shale & lime	2700
lime	2755
shale & lime	3000
lime brkn	3095
shale & lime	3230
lime	3295
shale & lime	3360
lime	3465
lime & shale	3500
shale & conglomerate	3605
Total Depth	

Geol. Data:
Top Lansing-K.C. 3212
Top Arbuckle ?? 3602
Residual Zone 3516

FILE
BOOK
11 9 1946
57 13
STATE COMMISSION
NOV 4 - 1946
DIVISION



15-163-02899-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

June 8, 1946

IN REPLY PLEASE
REFER TO THIS
SUBJECT

Well No. 1
Lease Ruder
Description No. 38 11-9-19W
County Nooks
File: 57-13

The Aylward Production Co.
813 First National Bank Bldg.
Wichita 2, Kansas

Gentlemen:

This letter is your permit to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission.

Very truly yours,

STATE CORPORATION COMMISSION
CONSERVATION DIVISION

HA

BY: J. P. Roberts
J. P. ROBERTS

NOTICE: H. W. Kerr
Great Bend, Kansas

Received
11/4/46



STATE OF KANSAS
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 800 BITTING BUILDING
 WICHITA, KANSAS

October 18, 1946

IN REPLY PLEASE
 REFER TO THIS
 SUBJECT

The Aylward Production Co.
 813 First National Bank Bldg.
 Wichita 2, Kansas

IN ACCOUNT WITH Conservation Division, State Corporation Commission
 Wichita, Kansas

WE Charge YOU

Plugging Assessment.....\$ 25.00

*pd.
11/4/46
H.A.*

Well No. 1
 Farm Ruder
 Description NE NW SE 11-9-19W
 County Rooks
 File: 57-13

The assessment for the plugging of all wells in the State of Kansas is one cent per foot, with a maximum of \$25.00 and a minimum of \$5.00.

This assessment will be past due November 1, 1946

PLEASE RETURN ONE COPY WITH REMITTANCE

NOTE: We also need a log of this well, to complete the file.

attached hereto
[Signature]
 RECEIVED
 OCT 21 1946
 CONSERVATION DIVISION
 WICHITA, KANSAS



STATE OF KANSAS
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 800 BITTING BUILDING
 WICHITA, KANSAS

October 18, 1946

IN REPLY PLEASE
 REFER TO THIS
 SUBJECT

The Aylward Production Co.
 813 First National Bank Bldg.
 Wichita 2, Kansas

IN ACCOUNT WITH Conservation Division, State Corporation Commission
 Wichita, Kansas

WE Charge YOU

Plugging Assessment.....\$ **25.00**

Well No. **1**
 Farm **Ruder**
 Description **NE NW SE 11-9-197**
 County **Rooks**
 File: **57-13**

The assessment for the plugging of all wells in the State of Kansas is one cent per foot, with a maximum of \$25.00 and a minimum of \$5.00.

This assessment will be past due November 1, 194 6

PLEASE RETURN ONE COPY WITH REMITTANCE

NOTE: We also need a log of this well, to complete the file.

THE AYLWARD PRODUCTION COMPANY
813 FIRST NATIONAL BANK BUILDING
WICHITA 2, KANSAS

October 8, 1946

State Corporation Commission
800 Bitting Building
Wichita, Kansas

Dear Sirs:

We are herewith enclosing Well Plugging Record covering our Ruder No. 1, located in the NE/4 NW/4 SE/4 of Section 11-9S-19W, Rocks County, Kansas.

Yours very truly,

THE AYLWARD PRODUCTION COMPANY

By

Al Skalsky/mmb

11 9 1946
57 13

