

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

ROOKS County, Sec. 11 Twp. 9 S Rge. 19 (X) W (W)

Location as "NE/CNW/SW" or footage from lines CS 1/2 SW SW

Lease Owner Meadowlark Drig., Inc.

Lease Name Thyfault Well No. 1

Office Address 1823 Washington, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed Oct. 1 19 59

Application for plugging filed Oct. 1 19 59

Application for plugging approved Oct. 1 19 59

Plugging commenced Oct. 1 19 59

Plugging completed Oct. 1 19 59

Reason for abandonment of well or producing formation Not Productive

If a producing well is abandoned, date of last production - 19 -

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Beldon Petty

Producing formation Arbuckle Depth to top 3476 Bottom 3523' Total Depth of Well 3523' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fluid level was 200' Ran 1 wood & rubber plug to 550' and mixed 20 sxs common cement by hand method on top of this plug thru d.p. Filled hole w/mud to 180' & ran 1 8 5/8" wood & rubber plug & 1/3 sx hulls to 180' & mixed 15 sxs common cement on top of plug thru dp. Filled hole w/mud to 40' & ran 1 wood & rubber plug to 40 w/1/3 sx hulls on top & cemented w/10 sxs common cement; cement to bottom of cellar.

Plugging commenced @ 5.00 P.M. 10/1/59 completed

@ 8:30 P.M. 10/1/59.

RECEIVED
STATE CORPORATION COMMISSION
10/21/59
OCT 21 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Meadowlark Drig. Inc.

Address 1823 Washington, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

W. L. Luther (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. L. Luther

(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of October, 1959

Debra Miner

My commission expires Sept. 29, 1963

Notary Public.



15-163-19306-00-00

RECEIVED
CORPORATION COMMISSION
10/21/59
OCT 21 1959

SOONER OIL COMPANY
Tulsa 3, Oklahoma

EXPLORATION DIVISION

Thyfault No. 1

SW 1/4 Sec. 11-9S-19W
Rooks County, Kansas

Commenced RD: 9-21-59
Completed RD: 10-2-59
Total Depth: 3523'

Elevation: 2042' G.L.
Initial Prod: D & A
Contractor: Meadowlark
Drilling, Inc.

Casing: 225.62' of 8 5/8" 8 rd.thd.

Strata	Depth
Surface Clay	0- 35'
Shale & Shells	35- 220
Shale, Shells & Redbed	220- 695
Shale & Shells	695- 930
Sand	930-1170
Redbed & Shale	1170-1440
Anhydrite	1440-1475
Shale & Shells	1475-1985
Lime (Ft. Riley)	1985-2385
Shale & Lime	2385-2988
Lime	2988-3002
Lime & Shale	3002-3130
Lime	3130-3193
Hebenir Lime	3193
Lime	3193-3215
Toronto Lime	3215
Lime	3215-3236
Lime (Kansas City)	3236-3453
Lime	3453-3478
Lime (Arbuckle)	3478-3523

I hereby certify that the above is a true & correct log of said well as reflected by the daily drilling reports.

MEADOWLARK DRILLING, INC.

By [Signature]

Signed and sworn to in my presence this 19th day of October, 1959.

[Signature]
Notary Public

My commission expires: Sept. 29, 1963