

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-163-19307-00-01

API NUMBER Completed 07/13/50

LEASE NAME Chandler SWD

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER D01

330 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 11 TWP. 9S RGE. 19 (E) or (W)

COUNTY Rooks

Date Well Completed 07/13/50

Plugging Commenced 03/15/91

Plugging Completed 03/20/91

LEASE OPERATOR Phillips Petroleum Company

ADDRESS Route 3, Box 20-A, Great Bend, Kansas 67530

PHONE# (316) 793-8421 OPERATORS LICENSE NO. 5229

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 03/06/91 (date)

by Dennis Hamel (in phone conversation w/ Jim Arroyo) (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Arbuckle Depth to Top 3624' Bottom 3908' T.D. 3908'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		224	0'	10 3/4"	224	0
		3624	0	7"	3624	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Connected to 7" casing. Pumped 100 sx Class A w/1/4# flocele per sk followed by 475 sx 65/35 Pozmix w/10% gel and 1/4# flocele per sk. Mixed 600# hulls w/1st 300 sx cement. Shut in w/100# pressure on 7". Topped off w/2 yds Redi-Mix. Cut off casing 7' below GL. Welded plate on showing "PPCo well name and date plugged".

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Phillips Petroleum Company License No. 5229

Address Route 3, Box 20-A, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Phillips Petroleum Company

STATE OF Kansas COUNTY OF Barton, ss.

J. W. Taylor (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature)

(Address) Route 3, Box 20-A, Great Bend, KS

SUBSCRIBED AND SWORN TO before me this 8th day of May, 1991

RECEIVED
STATE CORPORATION COMMISSION
5/9/91
MAY 09 1991

CONSERVATION DIVISION My Commission Expires: 10-23-92
Wichita, Kansas



Form CP-4
Revised 05-88

Formation Record

Lease **Thyfault** (Chandler Pool S.W.D. System) Well No. **1**

FROM	TO	Formation	REMARKS
0	45	Surface Soil	
45	230	Shale	
230	733	Sand and Shale	
733	1050	Shale and Shells	
1050	1245	Sand Lime	
1245	1350	Sandy Shale	
1350	1428	Shale	
1428	1460	Anhydrite	
1460	1800	Shale	
1800	1915	Shale and Shells	
1915	2175	Lime and Shale	
2175	2245	Shale	
2245	2285	Lime	
2285	2385	Lime and Shale	
2385	2515	Shale and Shells	
2515	2680	Lime and Shale	
2680	2825	Shale and Shells	
2825	2975	Shale, Lime and Shells	
2975	3097	Lime and Shale	
3097	3513	Lime	
3513	3535	Lime - Hard - Rough	
3535	3539	Lime	
3539	3559	Lime - Hard - Rough	
3559	3579	Lime - Pyrite and Chert	
3579	3612	Sandy Lime	
3612	3643	Sand, Lime and Pyrite	
3643	3673	Lime - Pyrite	
3673	3790	Sandy Lime	
3790	3848	Lime and Chert	
3848	3881	Lime	
3881	3890	Lime and Sand	
3890	3901	Chert	
3901	3908	Granite Wash	

Top Granite Wash @ 3885'.

RECEIVED
STATE CORPORATION COMMISSION

MAY 09 1991

CONSERVATION DIVISION
Wichita, Kansas