


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rocks _____ County. Sec. 4 Twp. 9 Rge. 19 (E) 19 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines Gen West Line NE SE
Lease Owner Westgate-Greenland Oil Company
Lease Name McClellan "B" Well No. 3
Office Address 1022 Union National Bank Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed March 30, 1949 19
Application for plugging filed December 8, 1949 19
Application for plugging approved December 8, 1949 19
Plugging commenced December 17, 1949 19
Plugging completed January 1, 1950 19
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes
Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface		0	230	8 5/8"	230	none
Arbuckle			3455	5 1/2"	3455	727 feet

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. mud
Filled hole with heavy from 3455 to 3450 feet.
Run 5 sacks cement from 3450 to 3415 feet.
Filled with heavy mud from 3415 feet to 230 feet
Run 15 sacks cement from 230 to 200 feet.
Filled with heavy mud from 200 to 20 feet and
run 10 sacks cement to cellar base.

INTERRUPTED

1/12/50
JAN 12 1950

KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Westgate-Greenland Oil Company
Address 1022 Union National Bank Building, Wichita 2, Kansas


STATE OF Kansas, COUNTY OF Sedgwick, ss.
G. E. Bitler (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. E. Bitler
1022 Union National Bank Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of January, 19 50

Esther Tinsell
Notary Public.

My commission expires May 25, 1953



COMPANY: Westgate Greenland Oil Company
 CONTRACTOR: Jackson Drilling Corporation
 FARM: McClellan B-3
 LOCATION: OWL NE SE Section 4-9-19W
 Rooks County, Kansas
 ELEVATION: 2019
 COMMENCED: March 10, 1949
 COMPLETED: March 21, 1949 - Rotary
 March 30, 1949 - Cardwell

0	to	185	Shale & shells
185	to	550	Shale
550	to	640	Sand
640	to	915	Sandy shale
915	to	1155	Sand
1155	to	1440	Shale & Red bed
1440	to	1480	Anhydrite
1480	to	1585	Shale & shells
1585	to	1690	Red bed Shale & shells
1690	to	2235	Shale & shells
2235	to	2360	Lime & Shale
2360	to	2435	Shale & shells
2435	to	3336	Lime & shale
3336	to	3457	Lime

3457 T.D. Rotary
 3466 T.D. Cardwell

8 5/8" casing set at 230 feet. Cemented with 125 sacks cement.

5 1/2" casing set at 3455 feet. Cemented with 65 sacks cement.

Top Arbuckle - 3453

Acidized - 500 gallons Dowell service - 1000 gallons additional Dowell Service

Dry

Measurements taken from top of derrick floor

C E R T I F I C A T E

I, Clare A. Stewart, do hereby certify that the above and foregoing is a true and correct copy of log of the McClellan B-3, Section 4-9-19W, Rooks County, Kansas, as reflected by files of the Jackson Drilling Corporation.

Clare A. Stewart
 Clare A. Stewart

Subscribed and sworn to before me, a Notary Public, within and for Johnson County, Kansas, this 27th day of April, 1949.

Dorothy J. Wilson
 Dorothy J. Wilson

My Commission expires November 30, 1950

RECEIVED
 Conservation Div.
 DEC 8 - 1949
 COMMISSION

PLUGGING
 FILE NO. 4-9-19W
 PAGE 128 LINE 42