

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County, Sec. 4 Twp. 9S Rge. 19W (E) (W)

Location as "NE/CNW/SW" or footage from lines SE/4 NE/4 SW/4

Lease Owner The El Dorado Refining Co.

Lease Name McClellan Well No. 1

Office Address El Dorado, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed September 28, 19 56

Application for plugging filed (verbal) September 28, 19 56

Application for plugging approved (verbal) September 28, 19 56

Plugging commenced September 28, 19 56

Plugging completed September 29, 19 56

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty, Hays, Kansas

Producing formation None Depth to top Bottom Total Depth of Well 3472 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
None	None	0	228'	8 5/8"	221'	None
No oil string - D & A						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 220', set bottom plug at 220' with 15 sacks cement and 1/2 sack Hulls.

Filled hole with heavy mud to 40', set top plug at 40' with 10 sacks cement and 1/2 sack Hulls.

12/22/56
DEC 22 1956
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Walters Drilling Co.
Address 510 Orpheum Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Robert F. Walters

(employee of owner) or ~~Walters Drilling Co.~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert F. Walters
510 Orpheum Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of October, 19 56

Pauline Hendrickson
Notary Public.

My commission expires March 10, 1960

PLUGGING
SEC 4 T 9 R 19W
DECL 127 11 10
104 2

McCLELLAN NO. 1

Location: SE/4 NE/4 SW/4 Sec. 4-9S-19W
Rooks County, Kansas

Date Spudded: 9-19-56

Operator: The El Dorado Refining Co.

Completion: 9-28-56

Contractor: Walters Drilling Co.

Elevation: 1986 Gr
1988 DF
1991 KB

Surface Casing: 8 5/8" set at 228' with
150 sacks cement and 2
Cal. Chloride

Oil String: None. D & A

L O G

(Figures indicate bottom of formation)

Surface	0 to 228
Shale and Shells	890
Sand	1130
Shale and Shells	1405
Anhydrite	1440
Shale and Shells	2130
Shale and Lime	3174
Lime	3420
Lime and Shale	3472
Total Depth	3472

The undersigned, Robert F. Walters, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above noted well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO.

By

Robert F. Walters

Subscribed and sworn to before me
this 1st day of October, 1956

Pauline Hedrickson

Notary Public

My commission expires:
March 10, 1960

RECEIVED
STATE CORPORATION COMMISSION

CCMR

