

15-163-03413-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER Spud 8/1/55  
LEASE NAME McMillen  
WELL NUMBER #1  
2970 Ft. from S Section Line  
990 Ft. from E Section Line  
SEC. 25 TWP. 8 RGE. 18 (X) or (W)  
COUNTY Rooks

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR The Dane G. Hansen Trust  
ADDRESS P. O. Box 187, Logan, Kansas 67646  
PHONE#(913) 689-4816 OPERATORS LICENSE NO. 5285

Date Well Completed 8/9/55  
Plugging Commenced 10:45 A.M. 10/12/93  
Plugging Completed 12:00 P.M. 10/12/93

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on October 12, 1993 (date)  
by Card Goodrow (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation LKC Depth to Top \_\_\_\_\_ Bottom T.D. 3432

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	165'	None
				5 1/2"	3411'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Run tubing to 2000', spot 75 sx and 2 hulls pulled to 1000', mixed 70 sx and 2 hulls and circ to surface, pulled tubing out, tied on to 5 1/2" mixed 80 sx and 2 hulls. Max Press 500#. Shut in at 400 PSI

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. \_\_\_\_\_  
Address P. O. Box 31, Russell, Kansas 67665

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 14 1993  
OCT 14 1993  
CONSERVATION DIVISION  
Wichita, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: The Dane G. Hansen Trust  
STATE OF KANSAS COUNTY OF PHILLIPS, ss.

Dane G. Bales, (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dane G. Bales  
(Address) P. O. Box 187, Logan, Kansas 67646

SUBSCRIBED AND SWORN TO before me this 13 day of October, 19 93

Betty Jane Bittel  
Notary Public  
My Commission Expires: July 17, 1996

CONTRACTOR'S WELL LOG

OPERATOR D. G. HANSEN WELL NAME McMILLEN #1  
 WELL LOCATION SW/4 SE/4 NE/4 Sec. 25-8S-18W  
 POOL NAME ELM CREEK COUNTY ROOKS STATE KANSAS  
 COMMENCEMENT DATE AUGUST 1, 1955 COMPLETION DATE August 9, 1955

LOG OF WELL

Elevation 1997 Rotary Bushing.  
 All measurements from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	165	Sand-Shale		
165	520	Shale		
520	630	Sand		
630	700	Shale		
700	765	Shale		
765	1030	Sand-Shells		
1030	1312	Sand-Red Bed		
1312	1347	Anhydrite		
1347	1400	Shale		
1400	1840	Shale-Shells		
1840	2040	Lime-Shale		
2040	2160	Lime-Shale		
2160	2310	Lime-Shale		
2310	2430	Lime-Shale		
2430	2530	Lime-Shale	0° - 2500'	
2530	2635	Lime-Shale		
2635	2775	Lime-Shale		
2775	2915	Lime-Shale	0° - 2750'	
2915	2985	Lime-Shale		
2985	3036	Lime-Shale	0° - 3000'	
3036	3100	Lime-Shale		
3100	3160	Lime-Shale		DST 3152-3160'
3160	3165	Lime-Shale		
3165	3215	Lime-Shale		
3215	3263	Lime-Shale		
3263	3311	Lime-Shale	0° - 3250'	DST 3303-3311'
3311	3322	Lime-Shale		DST 3316-3322'
3322	3345	Lime-Shale		
3345	3413	Lime-Shale		

CASING LEFT IN HOLE AFTER COMPLETION

Set 165' of 8-5/8" OD Surface Casing (8 jts.).

Ran 3423.52' of 5-1/2" OD Production String of Casing (107 jts.).

STATE OF KANSAS, COUNTY OF SEDGWICK ) ss.

The undersigned certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By Jay H. Galloway RECEIVED  
 STATE CONSERVATION COMMISSION

Subscribed and sworn to before me this 11th day of August, 1955.

Vicky Jacobs OCT 14 1993  
 Notary Public CONSERVATION DIVISION  
 Wichita, Kansas

My commission expires: 5/20/59