

15-163-03414-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER Spud 8/11/55

LEASE NAME McMillen

WELL NUMBER 2

3630 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 25 TWP. 8 RGE. 18 (E) or (W)

COUNTY Rooks

Date Well Completed 8/27/55

Plugging Commenced 1:20 P.M. 9/14/93

Plugging Completed 2:00 P.M. 9/14/93

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR The Dane G. Hansen Trust

ADDRESS P. O. Box 187, Logan, Kansas 67646

PHONE# (913) 689-4816 OPERATORS LICENSE NO. 5285

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on September 14, 1993 (date)

by Marion Schmidt (KCC District Agent's Name).

Is ACO-1 filed?                      If not, is well log attached? Yes

Producing Formation                      Depth to Top                      Bottom T.D. 3394  
P.B.T.D. 3290

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	160'	None
				5 1/2"	3390'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Down 4 1/2" Liner mixed 25 sks. cement followed with 500# hulls.  
Mixed in 190 sks cement. Max. Press 800#. Shut In 500#.  
Down 8 5/8' casing, pressured to 500#. No cement.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No.                     

Address P. O. Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: The Dane G. Hansen Trust

STATE OF KANSAS COUNTY OF PHILLIPS, ss.

Dane G. Bales, Manager (Employee of Operator) or (Operator) of above-described well, being first July sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 17 1993  
(Signature) Dane G. Bales  
(Address) P. O. Box 187, Logan, Kansas 67646

SUBSCRIBED AND SWORN TO before me this 15 day of September, 19 93



CONSERVATION DIVISION  
Wichita, Kansas  
Betty Jane Bittel Notary Public

My Commission Expires: July 17, 1996.

15-163-03414-00-00

CONTRACTOR'S WELL LOG

OPERATOR D. G. HANSEN WELL NAME McMILLEN #2  
WELL LOCATION NE/4 SE/4 NE/4 Sec. 25-8S-18W.  
POOL NAME ELM CREEK COUNTY ROOKS STATE KANSAS  
COMMENCEMENT DATE AUGUST 11, 1955 COMPLETION DATE AUGUST 19, 1955

LOG OF WELL

Elevation 1977 rotary bushing.  
All measurements from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	160	Sand-Shale		
160	840	Sand-Shale		
840	1010	Sand		
1010	1025	Shale		
1025	1298	Red Bed		
1298	1338	Anhydrite		
1338	1530	Shale-Shells		
1530	1790	Shale-Lime		
1790	2040	Shale-Lime		
2040	2175	Lime-Shale		
2175	2395	Lime-Shale		
2395	2495	Lime-Shale	0	
2495	2650	Lime-Shale	0° - 2500'	
2650	2815	Lime-Shale	0° - 2750'	
2815	2925	Lime-Shale		2879' Topeka
2925	3000	Lime-Shale	0° - 3000'	
3000	3076	Lime-Shale		3091' Heebner
3076	3135	Lime-Shale		1. DST 3133-40'
3135	3150	Lime-Shale		3111' Toronto
3150	3214	Lime-Shale		3131' Lansing
3214	3250	Lime-Shale	0° - 3250'	
3250	3289	Lime-Shale		2. DST 3280-89'
3289	3302	Lime-Shale		3. DST 3294-3302'
3302	3391	Lime-Shale		3354' Base K. C.
3391	3394	Lime		3389' Arbuckle

CASING LEFT IN HOLE AFTER COMPLETION

Set 160.41' of 8-5/8" OD Surface Casing.  
Rang 3398.58' (105 jts.) of 5-1/2" OD Casing.  
STATE OF KANSAS, COUNTY OF SEDGWICK ) ss.

The above undersigned certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway  
G. F. Galloway

Subscribed and sworn to before me this 22nd day of August, 1955.

My commission expires: 5/20/59

Wick Jacobs  
Notary Public

RECEIVED  
AUG 23 1955  
A. G. CUMMING

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 23 1955  
JUL 21 1993  
D. G. Hansen, JUL 21 1993  
CONSERVATION DIVISION  
Wichita, Kansas

15-163-03414-00-00

Perforations: 3299-3307; 3110-13; 3130-34; 3206-09; 3216-18; 3226-30;; 3282-84;  
2980-81

Squeezes: 2522-53 w/50 sx; 705-736 w/200 sx; 2283-2314 w/250 sx; 2430-68 w/50 sx;  
740-779 w/200 sx; 2130-2572 w/300 sx.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 21 1993  
JUL 21, 1993  
CONSERVATION DIVISION  
Wichita, Kansas