

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-163-19137-00-00

API NUMBER Spud 12/3/59

LEASE NAME McMillen

WELL NUMBER #3

3630 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 25 TWP. 8 RGE. 18 (E) or (W)

COUNTY Rooks

Date Well Completed 12/3/59

Plugging Commenced 8:45 A.M. 10/11/93

Plugging Completed 10:45 A.M. 10/11/93

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR The Dane G. Hansen Trust

ADDRESS P. O. Box 187, Logan, Kansas 67646

PHONE#(913) 689-4816 OPERATORS LICENSE NO. 5285

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on October 11, 1993 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation LKC Depth to Top \_\_\_\_\_ Bottom T.D. 3415

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	157'	None
				5 1/2"	3405'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Pump down Annulus w/5 sacks cement, press. to 200PSI. Pump down 5 1/2" casing w/200 sx cement plus 500# hulls. Max PSI 300; Shut In PSI 250.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. \_\_\_\_\_

Address P. O. Box 31, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: The Dane G. Hansen Trust

STATE OF KANSAS COUNTY OF PHILLIPS, ss.

Dane G. Bales (Employee of Operator) or \_\_\_\_\_ of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dane G. Bales

(Address) P. O. Box 187, Logan, Kansas 67646

SUBSCRIBED AND SWORN TO before me this 12 day of October, 19 93

BETTY JANE BITTEL  
State of Kansas  
My Appt. Exp. July 17, 1996

My Commission Expires: July 17, 1993. Betty Jane Bittel Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 13 1993  
OCT 13 1993  
CONSERVATION DIVISION  
Wichita, Kansas

W E L L L O G

OPERATOR D. G. Hansen

SEC. 25-8-18W

WELL NAME McMillan #3

LOC. NW SE NE

TOTAL DEPTH 3414'

COUNTY Rooks

COMM. December 3, 1959 COMP. December 12, 1959

STATE Kansas

RIG NO. 1

ELEVATION 1989' K.B.

CASING: Ran 157.78' (8 jts.) 8-5/8" OD Surface Casing.  
Set 5-1/2" OD Casing @3405' (107 jts.)

PRODUCTION: Producing

All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	860	Shale-Sand		
860	1015	Sand		
1015	1065	Red Bed		
1065	1306	Shale-Red Bed		
1306	1348	Anhydrite		
1348	1440	Shale-Shells		
1440	1875	Shale-Shells		
1875	2160	Lime-Shale		
2160	2310	Shale-Lime	0° - 2500	
2310	3110	Lime-Shale	0° - 2750	
3110	3210	Lime	0° - 3000	DST 3134-3156'
3210	3247	Lime-Shale		DST 3171-3210'
3247	3355	Lime		DST 3230-3247'
3355	3414	Lime-Shale	0° - 3250	DST 3292-3327'

STATE OF KANSAS }  
COUNTY OF SEDGWICK } SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.  
By G. F. Galloway

SUBSCRIBED AND SWORN TO, BEFORE ME, THIS 15th day of December, 1959.

My commission expires: May 20, 1963

Vicky Jacobs  
Notary public

RECEIVED  
STATE CORPORATION COMMISSION

OCT 13 1993  
OCT 13, 1993  
CONSERVATION DIVISION  
Wichita, Kansas