

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 163-01,027-00-01  
LEASE NAME Peter Dechant

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER #2  
2310 Ft. from S Section Line  
2310 Ft. from E Section Line

LEASE OPERATOR The Gene Brown Company

SEC. 26 TWP. 8 RGE. 18 ~~XXX~~ (W)

ADDRESS P.O. Drawer 220 Plainville, Ks. 67663

COUNTY Rooks

PHONE# (913) 434-4811 OPERATORS LICENSE NO. 5635

Date Well Completed 9-27-90

Character of Well OWWO

Plugging Commenced 9-28-90

(Oil, Gas, Water, or Other Fluids)

Plugging Completed 9-28-90

The plugging proposal was approved on 9-27-90 (date)

by Marion Schmidt - District #4 (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? none

Producing Formation LKC - Arbuckle Depth to Top 3141 Bottom 3446 T.D. 1025

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
surface	fresh water			8 5/8	230	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Drilled 1st plug cement o-40' - Drilled 2nd plug = Wiper rubber and cement  
167-220' - Drilled 3rd plug = wiper rubber at 640' and went out old hole.  
Drilled to 1025'. Called for plugging orders - Cement order / 200 sks 60/40poz  
6% gel 3% cc. - Wiper // 1st plug 50 sks at 1020' / 2nd plug 100 sks with(See  
(If additional description is necessary, use BACK of this form.) back)

Name of Plugging Contractor Halliburton Services License No. 5287

Address Hays, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: The Gene Brown Company

STATE OF Kansas COUNTY OF Rooks, ss.

Thomas M. Brown (Employee of Operator) ~~XXXXXX~~ of  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,  
statements, and matters herein contained and the log of the above-described well as filed that  
the same are true and correct, so help me God.


(Signature) Thomas M. Brown

(Address) P.O. Drawer 220 Plainville, Ks 67663

SUBSCRIBED AND SWORN to before me this 8<sup>th</sup> day of October, 19 90

My Commission Expires: 5-27-94

Notary Public



flowcele at 770' / 3rd plug 40 sks at 270' / 4th plug wiper rubber  
10'sks 40' to surface.