

15-163-02560-00-00

WELL PLUGGING RECORD

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

OR  
FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

..... Rooks ..... County. Sec. 29 Twp. 8 Rge. 19 (E) W (W)  
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines.....  
Lease Owner Sam Pack et al  
Lease Name Gaylord Well No. 1  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed August 15, 1951 19.....  
Application for plugging filed August 15, 1951 19.....  
Application for plugging approved August 15, 1951 19.....  
Plugging commenced August 15, 1951 19.....  
Plugging completed August 15, 1951 19.....  
Reason for abandonment of well or producing formation dry hole  
If a producing well is abandoned, date of last production..... 19.....  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? yes

NORTH



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well.....  
Producing formation..... Depth to top..... Bottom..... Total Depth of Well 3556 Feet  
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to  
.....feet for each plug set.

Filled with heavy rotary mud every 500 feet while coming out of hole.  
Set plug at 200 feet and cemented with 15 sacks of cement.  
Filled with heavy rotary mud to 40 feet and cemented with 10 sacks of cement



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to J. W. Braden Drilling Company  
Address P. O. Box 266, Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.  
J. W. Braden (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-  
described well as filed and that the same are true and correct. So help me God.

(Signature) J. W. Braden  
Hutchinson, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 31st day of August, 1951

My commission expires March 21, 1953

M. L. Bowman  
Notary Public.

22-2625 2-48-15M  
PLUGGING  
OIL REC-29 T 8 R19W  
BOOK PAGE 104 LINE 0

15-163-02560-00-00

GAYLORD #1

Location -29-19\* 8-19 W, Rooks County, Kansas

Contractor - J. W. Braden Drilling Company

Company - Sam Pack et al

Date Started - August 4, 1951

Date Finished - August 15, 1951

Surface clay	65	
Shale & Shells	595	
Sand	715	
Shale & shells	1040	
Dakota Sand	1250	
Shale	1475	
Sharp Sand	1550	
Hard Sand	1580	
Sandy Red Shale	1780	
Shale	1855	
Lime & Shale	2085	
Lime	2230	
Shale & Lime	2960	
Lime	3090	
Lime & Shale	3230	
Lime	3556	T.D.

CASHING RECORD

228' of 8-5/8" cemented with 110 sacks cement

STATE OF KANSAS )  
                          )SS:  
COUNTY OF RENO  )

I hereby certify that the above information is true and correct to the best of my knowledge.

J. W. Braden SEP 1 1951  
CONSERVATION DIVISION  
WICHITA, KANSAS

Subscribed and sworn to before me this 31st day of August, 1951.

M. L. Bowman  
Notary Public

My Commission expires:  
March 21, 1953

**PLUGGING**  
FILE SEC 29 T 8 R 19W  
BOOK PAGE 104 LINE 10