


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

15-143-00132
~~00442~~-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rocks _____ County. Sec. 33 Twp. 8S Rge. (E) 19 (W)
Location as "NE/CNW/SW" or footage from lines SW SW NE
Lease Owner Natural Gas and Oil Company
Lease Name LOWRY Well No. 1
Office Address Box 105, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed July 31 19 48
Application for plugging filed Sept. 15 19 56
Application for plugging approved Sept. 17 19 56
Plugging commenced Sept. 15 19 56
Plugging completed Sept. 20 19 56
Reason for abandonment of well or producing formation Oil Production Depleted

If a producing well is abandoned, date of last production Sept. 10 19 56
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Lansing Lansing Depth to top 3248 Bottom 3252 Total Depth of Well 3453 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface				10 3/4"	157'	None
Oil String				5 1/2"	3450'	2577'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into T.D. 3452'
Plugging started 9-15-56; finished 9-20-56
Plugged off bottom with sand to 3200' and dumped 4 sacks cement with bailer and shot 5 1/2" casing at 2559'. Pulled pipe out of hole and plugged well with heavy mud to 155' and set permanent rock bridge. Dumped 20 sacks cement. Filled hole with heavy mud to 30' and mixed 10 sacks for cap on well.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J. O. Forbes d/b/a Forbes Casing Pulling Company
Address Box 221, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
J. B. Steele, Jr. (employee of owner) or (owner or operator)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. B. Steele, Jr.

Box 105, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of September, 1956

Richard R. Brach
Notary Public.

My commission expires July 27, 1956

cc: Corporation Commission
New Orleans - 2
Wichita
File

PLUGGING
FILE SEC. 33 T. 8 R. 19W
BOOK PAGE 99 LINE 10

RECEIVED
SEP 26 1956

10/1/56

15-163-00132
~~00142-00-00~~

D R I L L E R S L O G

COMPANY: Westgate Greenland Oil Company
CONTRACTOR: Jackson Drilling Corporation
FARE: Lowry #1
LOCATION: SW SW NE Section 33-8S-19W
Rooks, County, Kansas
ELEVATION: 2012'
COMMENCED: July 5, 1948
COMPLETED: July 17, 1948 - Rotary
July 31, 1948 - Cardwell

0	to	100	Shale & shells
100	to	540	Shale & shells
540	to	570	Sand
570	to	1415	Red Bed
1415	to	1455	Anhydrite
1455	to	1750	Shale & shells
1750	to	1950	Lime, shale and shells
1950	to	2410	Lime & Shale
2410	to	2530	Lime
2530	to	2595	Lime & Shale
2595	to	2650	Shale
2650	to	2870	Lime
2870	to	3060	Lime & Shale
3060	to	3454 T.D. Rotary	Lime
2454	to	3455 T.D. Cardwell	Lime
		3453 $\frac{1}{2}$ T.D. Plugged back	

10 3/4" casing set at 157 feet. Cemented with 150 sacks cement.

5 1/2" casing set at 3450 feet. Cemented with 65 sacks cement.

Swabbed 1 $\frac{1}{2}$ bbls. oil per hour plus 25% water

All measurements from Derrick Floor

Potential - 35 Barrels - 12/8

C E R T I F I C A T E

I, Clare A. Stewart, do hereby certify that the above and foregoing is a true and correct copy of log for the Lowry #1, Section 33-8S-19W, Rooks County, Kansas, as reflected by files of the Jackson Drilling Corporation.

Clare A. Stewart

Subscribed and sworn to before me, a Notary Public, within and for Johnson County, Kansas, this 15th day of September, 1948.

~~Dorothy J. Wilson~~

Dorothy J. Wilson

My Commission expires November 30, 1950

18/1/56
PLUGGING
FILE SEC 33 T 8 R 19W
BOOK PAGE 99 LINE 10

copy