

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15163-0145-00-00
LEASE NAME FIDELIS

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER NO. 2
990 Ft. from S Section Line
1650 Ft. from E Section Line

LEASE OPERATOR Phillips Petroleum Company

SEC. 33 TWP. 8S RGE. 19 (X) or (W)

ADDRESS Route #3, Box 20-A, Great Bend, KS 67530

COUNTY Rooks

PHONE# (316) 793-8421 OPERATORS LICENSE NO. 5229

Date Well Completed 08-30-48

Character of Well Oil

Plugging Commenced 11-18-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11-19-88

The plugging proposal was approved on 07-29-88 (date)

by Shari Feist (KCC District Agent's Name).

Is ACO-1 filled? _____ If not, is well log attached? _____

Producing Formation LKC Depth to Top 3171 Bottom 3408 T.D. 3436.5

Show depth and thickness of all water, oil and gas formations.

RECEIVED

STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Put Off

CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

MIRU Allied Cementing Co. to 5 1/2" csg. Mixed 12 sacks hulls & 175 sacks

Econolite cement w/1/4# per sack cellu-flakes. SI press 1000#. Conn to 8 5/8 -

5 1/2" annulus, mixed 2 sacks hulls & 100 sacks Econolite cement w/1/4# per sack

cellu-flakes. SI press 500#. RD & rel Allied Cementing. Cut csg off 10' below (over)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. License No. _____

Address N. Main Street, Great Bend, KS 67530


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Phillips Petroleum Company

STATE OF Kansas COUNTY OF Barton, ss.

A. R. Lyons (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) A. R. Lyons

(Address) Route #3, Box 20-A, Great Bend, KS



AND SWORN TO before me this 14th day of February, 1989

Candace A. Conwell

Notary Public

My Commission Expires: 07-30-90

ARL _____
CAC _____
FS _____
KES _____
DAR _____
MDS _____
GJH _____
CMY _____
File _____
Post _____
CC:GLK _____
CC:AMW _____

ground level. Welded plate over csg stub.

RECEIVED IN THE BUREAU OF THE
GENERAL INVESTIGATIVE
DIVISION OF THE FBI
JUL 1 1964

Formation Record

Lease

Fidelis

15-163-01415-00-00

Well No.

2

FROM	TO	Formation	REMARKS
0	6	Surface Soil	ELEVATION: 2004 R.T.B.
6	70	Sand and Shale	
70	830	Shale and Shells	
830	1200	Sand and Shale	
1200	1400	Shale and Red Bed	
1400	1412	Red Bed	Top Anhydrite at 1412'
1412	1445	Anhydrite	
1445	1450	Shale	
1450	2000	Shale and Shells	
2000	2050	Shale and Lime Shells	
2050	2375	Lime	
2375	2820	Shale	
2820	2940	Shale and Lime	
2940	3436 $\frac{1}{2}$	Lime	Top Heebner 3145 Top Toronto 3167 Top L.K.C. 3184 Top Arbuckle 3431

RECEIVED
STATE CORPORATION COMMISSION

JUL 27 1988

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUL 29 1988

CONSERVATION DIVISION
Wichita, Kansas

7/29/88

RECEIVED
STATE CORPORATION COMMISSION

JUL 29 1988

CONSERVATION DIVISION
Wichita, Kansas