


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-163-01418-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks

County. Sec. 33 Twp. 8S Rge. 19W (W)

Location as "NE/CNW/SE/4" or footage from lines 330 fr. N & 990 fr. W, SE/4
Lease Owner Phillips Petroleum Company
Lease Name Fidelis Well No. 5
Office Address Box 779, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed October 31, 19 49
Application for plugging filed August 23, 19 56
Application for plugging approved August 24, 19 56
Plugging commenced September 21, 19 56
Plugging completed September 23, 19 56
Reason for abandonment of well or producing formation Uneconomical to operate.

If a producing well is abandoned, date of last production February 14, 19 55
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Milton Galyardt
Producing formation Arbuckle Depth to top 3415 Bottom NR Total Depth of Well PB3165 Feet
Show depth and thickness of all water, oil and gas formations. OTD 3422

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Anhydrite	Dry	1395	1430	8-5/8"	1440.96 OA	None
Howard	Dry	2926	2953	5-1/2"	3442.45 OA	2335'
Topeka	Dry	2953	3135			
Heebner	Dry	3135	3154			
Toronto	Dry	3154	3173			
Lansing-Kansas City	Dry	3173	3390			
Penn. Conglomerate	Dry	3408	3415			
Arbuckle	Oil	3415	3422			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Well was plugged back from 3422' TD to PETD of 3165' on previous reconditioning job.
Filled with sand from 3165' to 3140'. Dumped 4 sx. cement from 3140' to 3116'.
Mudded hole 3116' to 200'. Set 10' rock bridge and 15 sx. cement to 145'. Mudded hole to 35'. Set 5' rock bridge and 10 sx. cement in filling to base of cellar. Well plugged and abandoned at 12:00 Noon 9-23-56. FINAL REPORT.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
A. J. Willis (employee of owner) ~~or (owner or operator)~~ of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 779, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of September, 19 56

My commission expires November 18, 1957 [Signature] Notary Public.

PLUGGING
FILE SEC 33 T 8 R 19W
BOOK PAGE 92 LINE 37

9/25/56

15-163-01448-00-00

EXPLORATION RECORD

Phillips Petroleum Company - Fidelis No. 5 - 330' from North and 990' from West Lines, SE/4 Sec. 33-8S-19W, Rooks County, Kansas.

Lease Fidelis

Well 5

Formation Name	Top	Base	Remarks
Sand and Shale	0	390	
Shale and shells	390	781	
Sand, shale and shells	781	1176	
Shale, shells and redbed	1176	1395	
Anhydrite	1395	1404	
Anhydrite and shale	1404	1450	
Shale and shells	1450	1880	
Lime and Shale	1880	3002	
Lime	3002	3040	
Lime and shale	3040	3094	
Lime	3094	3382	
Lime	3382	3422	

FORMATION TOPS:

Anhydrite	1395
Howard	2926
Topeka	2953
Heebner	3135
Toronto	3154
LKC	3173
Penn. Conglomerate	3408
Arbuckle	3415

PLUGGING
 FILE SEC. 33 T 8 R 19W
 BOOK PAGE 92 LINE 37

9/25/56