

API NUMBER 15-163-21.340-0500

LEASE NAME Cerrow

WELL NUMBER #2

2310 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 33 TWP. 8 RGE. 19 (E/W)

COUNTY Rooks

Date Well Completed 7-10-81

Plugging Commenced 10-16-96

Plugging Completed 10-16-96

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR AFG Energy Inc.

ADDRESS P.O. Box 458 Hays, Kansas 67601-0458

PHONE# (913) 625-6374 OPERATORS LICENSE NO. 03456

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-14-96 (date)

by Marion Schmidt (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top 3453' Bottom 3460' T.O. 3460'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	Oil & Water	3453'	3460'	8 5/8"	261'	None.
				4 1/2"	3453	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set
Braden Head full of cement - Hooked to 4 1/2" Casing - Mixed 15 sxs. 60/40 Poz., 8% gel.
Followed with 300# HULLS and 100 sxs. 60/40 Poz., 8% gel. Pressured to 1500#. SIP - 1000#.
Total sxs. - 175.

Name of Plugging Contractor Allied Cementing License No. _____

Address Russell, Ks.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: AFG Energy Inc.


STATE OF Kansas COUNTY OF Ellis, ss.

Terry W. Piesker

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Terry W. Piesker

(Address) P.O. Box 458 Hays, Ks. 67601-0458



AND SWORN TO before me this 29th day of October, 19 96

Linda K. Pfannenstiel
 Notary Public

USE ONLY ONE SIDE OF EACH FORM
 My Commission Expires: 2/5/2000

15-163-21340-00-00

Cerrow #2

10-16-96

Cement in Barden Head. Hooked to 4 1/2" casing and mixed. Mixed 15 sxs. 60/40 Poz. 8% gel., then 300# of Hulls, followed by 160 sxs. 60/40 Poz. 8% gel. Pressured - 1500#. SIP - 1000#. Job complete. Total - 175 sxs.

11/1/96