

API NUMBER 15-163-21,643-02-122

LEASE NAME Cerrow

WELL NUMBER #3

1650 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 33 TWP. 8 SRGE. 19 (E/W or W)

COUNTY ROOKS

Date Well Completed 4/26/82

Plugging Commenced 10/16/96

Plugging Completed 10/16/96

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Coas. Div.
 office within 30 days.

LEASE OPERATOR AFG Energy Inc.

ADDRESS P.O. Box 458 Hays, Ks. 67601-0458

PHONE# (913) 625-6374 OPERATORS LICENSE NO. 03456

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10/14/96 (date)

by Marion Schmidt (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top 3453' Bottom 3460' T.O. 3460'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	OIL & WATER	3460'	3460'	8 5/8"	263	None
				5 1/2"	3453	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed from feet to feet each set.
Perforated 2 holes - 2000', 1437' & 840'. Ran 2 7/8" tubing to 3408'. Mixed 100 sxs. 60/40 Poz. 8% gel., and 400# Hulls. Displaced. Pulled up to 2004'. Circulated hole full with 130 sxs. 60/40 Poz., 8% gel and 100# Hulls. Pulled tubing. Tied to 8 5/8" and mixed 40 sxs. 60/40 Poz. 8% gel. Press. to 400# & blew hole in 8 5/8" - 1' below head. Hooked to 5 1/2" & squeezed out 50 sxs. same. Press. to 500#. SIP - 200#. -10/24/96 - Welded nipple & Valve on backside. Pressured to 500#. Held solid.

Name of Plugging Contractor Allied Cementing License No. _____

Address Russell, Ks.

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: AFG Energy Inc.


STATE OF Kansas COUNTY OF Ellis, ss.

Terry W. Piesker

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Terry W. Piesker

(Address) P.O. Box 458 Hays, Ks. 67601-0458



AND SWORN TO before me this 29th day of October, 19 96

Linda K. Pfannenstiel
 Notary Public

My Commission Expires: 2/5/2000
 USE ONLY ONE SIDE OF EACH FORM

Cerrow #3

15-163-21643-00-00

- 10-16-96 Perforated 2 holes each at 2000', 1437' and 840'. Ran 2 7/8" tubing to 3408'. Mixed 100 sxs. 60/40 Poz. 8% gel., and 400# Hulls. Displaced. Pulled tubing up to 2004'. Circulated hole full with 130 sxs. 60/40 Poz., 8% gel. and 100# Hulls. Pulled tubing out of hole. Tied to 5 1/2" casing. Mixed 40 sxs. 60/40 Poz., 8% gel., to 400#. Blew hole in casing 1' below Barden Head. Hooked to 5 1/2" and squeezed out 50 sxs. Pressured to 500#. SIP - 200#.
- 10-24-96 Allied hooked to casing and pressured to 500#. Cement 20' down.

11/1/96