

API NUMBER 15-163-03169-00-00

LEASE NAME Vallette

WELL NUMBER 1

\_\_\_\_\_ Ft. from S Section Line

\_\_\_\_\_ Ft. from E Section Line

SEC. 25 TWP. 8 S RGE. 18 (E) or (W)

COUNTY Rooks

Date Well Completed 7-13-49

LEASE OPERATOR Berexco, Inc.

ADDRESS P.O. Box 723 Hays, KS 67601

PHONE (785) 628-6101 OPERATORS LICENSE NO. 5363

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

RECEIVED  
MAY 22 2003  
MAY 22 2003

Plugging Commenced 5-2-03

Plugging Completed 5-5-03

The plugging proposal was approved on \_\_\_\_\_ (date)

by Bruce Bayse **KCC WICHITA** (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation LKC-ARB Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
Rig up Perf Tech. Shoot 2 holes ea @ 1845, 1400, 850, 235. Mix 100 SX 60/40 P02 10% gel w/300# hulls. Pull tbg. to 1613'. Mix 76 SX 60/40 P02 10% gel w/300# hulls. Pull tbg. to 600. Mix 50 SX 60/40 P02 10% gel w/200# hulls Circ. cement to surf. in 5 1/2 ann. Shut in 5 1/2 ann. Mix 60 SX cement to Circ. to surf. in 8 5/8 ann. Pull tbg. TOP off 5 1/2 csg. w/55 SX cement Jay Pfeifer witness - KCC Hays.

Name of Plugging Contractor Berexco, Inc. License No. 5363

Address \_\_\_\_\_

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Dennis Kirner (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.


(Signature) Dennis Kirner

(Address) PO Box 723, Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 16th day of May 2003

Marion Sue Vance  
Notary Public

My Commission Expires:



KCC

Form CP-1  
MAY 21 2003  
Revised 05-88

HAYS, KS