


STATE OF KANSAS  
 STATE CORPORATION COMMISSION

Give All Information Completely  
 Make Required Affidavit  
 Mail or Deliver Report to:  
 Conservation Division  
 State Corporation Commission  
 800 Bitting Building  
 Wichita, Kansas

OR  
**FORMATION PLUGGING RECORD** Strike out upper line when reporting plugging off formations.

Rooks County. Sec. 9 Twp. 8 Rge. 19 (E) 19 (W)  
 Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW SW  
 Lease Owner Petroleum Inc.  
 Lease Name A. E. Schneider Well No. 1  
 Office Address Derby Bldg., Wichita, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
 Date well completed 9-22 19 48  
 Application for plugging filed 9-22 19 48  
 Application for plugging approved 9-22 19 48  
 Plugging commenced 9-22 19 48  
 Plugging completed 9-22 19 48  
 Reason for abandonment of well or producing formation \_\_\_\_\_



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes  
 Name of Conservation Agent who supervised plugging of this well Rives  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
		0	270	8 5/8	9-11-48	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole filled with heavy mud - set plug @ 240' cemented with 15 sax cement. Filled hole on to top with heavy mud - set plug at 20', cemented with 10 sax cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Petroleum Inc.  
 Address Derby Bldg, Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss. 10-7-48  
J. W. Railsback (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) J. W. Railsback  
Box 163, Great Bend, Kan  
 (Address)

SUBSCRIBED AND SWORN TO before me this 1st day of Oct, 19 48  
Merle V. Sandifer  
 Notary Public.

My commission expires Oct 15, 1951

22-2625 2-48-15M  
**PLUGGING**  
 FILE SEC 9 T 8 R 19  
 BOOK PAGE 58 LINE 37

WELL LOG

Petroleum, Inc.,  
Schneider #1

Sec. 9-8-19W  
SW SW SW  
Rooks County, Kans.

Total Depth: 3495'  
Comm: 9-10-48 Comp.: 9-22-48  
Contractor: J.D.Ferrell Drilling Co., Inc.  
Issued: 9-20-48 Rotary: 0-3495'

Elevation: 1980'  
Production: Dry

Casing: 270' 8 5/8" Cemented with 135 sax cement.  
Cement circulated

Figures Indicate bottom of formations:

cellar	5		
clay & sand	40		
shale & shells	550		
sand & shale	700		
clay	810		
shale	890		
sand	1160		
shale & shells	1445	Tops:	
anhydrite	1465	Anhydrite	1445
sand & shale	1525	Heebner	3148
lime & shale	1680	Toronto	3171
shale & shells	3005	Lansing	3187
lime	3110	Arbuckle	3463
lime & shale	3150	Total Depth	3495
lime	3448	D & A	
lime & shale	3463		
arbuckle	3495		
Total Depth	3495		

We hereby certify this to be a correct and accurate log of the above described well as shown by the daily drilling reports.

J.D.FERRELL DRILLING COMPANY, INC.

By:

J.W. Rallsback  
J.W. Rallsback

Subscribed and sworn to before me this 30th day of Sept., 1948

My commission Expires:

Merle V. Sandgren  
Notary Public (Barber Co.)

Oct. 15, 1951

RECEIVED

DEC 24 1948  
STATE OF KANSAS  
COMMISSIONER

12-24-48

**PLUGGING**  
FILE SEC 9 T 8 R 19W  
BOOK PAGE 58 LINE 37