


15-163-20475-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rooks _____ County Sec. 12 Twp. 8S Rge. 19W (E) _____ (W) _____
Location as "NE/CNW/SW" or footage from lines. NE NW SE
Lease Owner Clinton Oil Company
Lease Name Opal Hance Well No. 1
Office Address 217 N. Water, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed March 9 19 73
Application for plugging filed March 9 19 73
Application for plugging approved March 9 19 73
Plugging commenced March 9 19 73
Plugging completed March 9 19 73
Reason for abandonment of well or producing formation _____
D&A
If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	230'	- 0 -

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole @ 660' W/70 Sx. - @ 220' W/20 Sx. -
@ 40' W/1 Sk. Halls, 10 Sx. Cement. 25 Sx. in
rat hole.

RECEIVED
STATE CORPORATION COMMISSION

MAR 16 1973

CONSERVATION DIVISION
Wichita, Kansas

3-16-73

Name of Plugging Contractor Red Tiger Drilling Company
Address 1720 Wichita Plaza, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Linda H. Dickens (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Linda H. Dickens

1720 Wichita Plaza, Wichita, Kansas 67202

(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of March, 19 73.

My commission expires 10-26-73

Marguerite Mayfield
Marguerite Mayfield

Notary Public.

15-163-20475-00-00

DRILLERS LOG

No. 1 "V" Opal Hance

CASING RECORD:

10 3/4" @ 230'
w/225 sx cement

TOTAL DEPTH: 3500'

COMPANY:

Clinton Oil Co.

CONTRACTOR:

Red Tiger Drilling Co.

COMMENCED:

March 2, 1973

COMPLETED:

March 9, 1973

DESCRIPTION:

NE NW SE
12-85-19W
Rooks County,
Kansas

ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Clay & Shale	0	230	
Shale	230	860	
Sand	860	1119	
Shale & Redbed	1119	1250	
Shale	1250	1404	
Anhydrite	1404	1440	
Shale & Shells	1440	1905	
Shale & Lime Streaks	1905	2165	
Shale & Lime	2165	2545	
Lime & Shale Streaks	2545	2700	
Shale & Lime	2700	2985	
Lime	2985	3400	
Lime & Conglomerate	3400	3442	
Lime	3442	3500	

RECEIVED
STATE CORPORATION COMMISSION
MAR 16 1973
CONSERVATION DIVISION
Wichita, Kansas


3-16-73

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Linda H. Dickens
Linda H. Dickens

Subscribed and sworn to before me this 14th day of March, 1973.



Gloria Fawcett
Notary Public

My Commission Expires:
October 25, 1976