

15-163-20178-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. 14 Twp. 8 Rge. (E)19 (W)
Location as "NE/CNW/SW" or footage from lines NE NW SE
Lease Owner J. Mark Richardson
Lease Name Hance Well No. 2
Office Address 502 Union Center Bldg. - Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Feb. 12, 19.69
Application for plugging filed Feb. 18, 19.69
Application for plugging approved Feb. 12, 19.69
Plugging commenced Feb. 12, 19.69
Plugging completed Feb. 12, 19.69
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3470 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	208'	8-5/8"	208'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 600 feet. Set first plug @ 600 feet w/70 sacks cement.
Filled hole with heavy mud to 180 feet. Set second plug @ 180 feet w/20 sacks cement.
Filled hole with heavy mud to 40 feet. Set third plug @ 40 feet w/10 sacks cement.
Plugged rat hole w/2 sacks cement. Job complete @ 11:15, Feb. 12, 1969.


RECEIVED
STATE CORPORATION COMMISSION
FEB 21 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Gabbert-Jones, Inc. 2-21-69
Address 830 Sutton Place, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
E. E. Hall (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. Hall
830 Sutton Place, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 18 day of February, 19 69



Feb. 1, 1972

Barbara J. Layton
Barbara J. Layton Notary Public.

15-163-20178-00-00

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

HANCE #2
NE NW SE Section 14-8S-19W
Rooks County, Kansas

Commenced: February 4, 1969
Completed: February 12, 1969

OPERATOR - J. Mark Richardson

DEPTH		FORMATION	REMARKS
From	To		
0	55	Surface clay and post rock	Ran 10 joints of 8-5/8" surface casing, set @ 208' w/150 sacks cement.
55	208	Sand and shale	
208	500	Shale	
500	600	Sand	
600	840	Shale and red bed	
840	875	Shale	
875	1110	Sand	
1110	1385	Red bed	
1385	1424	Anhydrite	
1424	1625	Shale and shells	
1625	2870	Shale and lime	
2870	3440	Lime	
3440	3445	Arbuckle	
3445	3470	Lime	
3470	TD		Dry and abandoned.

RECEIVED
STATE CORPORATION COMMISSION
FEB 21 1969
CONSERVATION DIVISION
Wichita, Kansas

2-21-69

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the NE NW SE Section 14-8S-19W, Rooks County, Kansas, to the best of my knowledge and belief.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 18 day of February, 1969, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972

Barbara J. Layton
Barbara J. Layton, Notary Public

