

15-103-02559-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Rocks _____ County. Sec. 15 Twp. 8 Rge. (E) 19 (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE $\frac{1}{4}$, NE $\frac{1}{4}$, NW $\frac{1}{4}$
Lease Owner Harbar & Polhamus
Lease Name Burton Well No. I
Office Address 1019 Central Bldg.
Character of Well (completed as Oil, Gas or Dry Hole) Rotary Dry Hole
Date well completed 11/18 1947
Application for plugging filed 11/18 1947
Application for plugging approved 11/18 1947
Plugging commenced 11/18 1947
Plugging completed 11/19 1947
Reason for abandonment of well or producing formation No production found



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production X 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation None Depth to top X Bottom X Total Depth of Well 3523 Feet
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface sands and clays	Trace fresh water	0	200	13" O.D.	66'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy drilling mud from 3523 to 200' ~~11/18~~
Bridged hole at 200' and pumped in 75 sx. cement through 2 line pipe filling hole with cement from 200' to bottom cellar. Cement pumped in by Halliburton Oil Well Cementing Company



12-3-47

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Harbar Drilling Company
Address 1019 Central Bldg. Wichita Kansas.

STATE OF Kansas, COUNTY OF Barton
H.L. King (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

H.L. King
(Address)

SUBSCRIBED AND SWORN to before me this 29 day of Nov, 1947

V.E. Fogelman
Notary Public.

My commission expires

30 Dec 1950

22-237 7-47-10M

PLUGGING
FILE SEC 15 T 8 R 19W
BOOK PAGE 148 LINE 34

BUNTON #1

NE $\frac{1}{4}$ NE $\frac{1}{4}$ NW $\frac{1}{4}$ of Sec. 15-8-19W, Rocks County, Kansas

Rigging up Rotary Tools 11-3-47
 Tearing down Rotary Tools 11-20-47

Set 13" casing at 66' and cemented with
 75 ex. of cement

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Surface sands and clays	0	90
Shale	90	460
Sandy Shale	460	537
Sand	537	745
Shale	745	930
Sand	930	1010
Sand and Shale	1010	1195
Shale and redbed	1195	1440
Anhydrite	1440	1475
Shale and shells - redbed	1475	1560
Shale and shells	1560	2085
Lime and shale	2085	2205
Lime and shale - mostly lime	2205	2295
Lime and shale	2295	3153
Shale	3153	3177
Lime	3177	3215
Lime and shale	3215	3250
Lime	3250	3290
Lime and shale	3290	3350
Lime	3350	3400
Shale and lime	3400	3451
Arbuckle	3451	3523 Total Depth

I, Don S. Packer, hereby certify that the above Log is true and correct, to the best of my knowledge and belief.

Don S. Packer

Subscribed and sworn to before me this 2nd day of December, 1947.

Mary R. Brown
 Notary Public

My commission expires: *Dec 23, 1950*

12-3-47

PLUGGING
 FILE SEC 15 T 8 19W
 BOOK PAGE 148 LINE 34