

15-163-02512-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Rooks County. Sec. 16 Twp. 8 Rge. 19 (E) (W)

Location as "NE1/4NW1/4SW1/4" or footage from lines SW SW SE

Lease Owner Jones, Shelburne & Farmer, Inc.

Lease Name Peterson Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry

Date well completed 6-2-48 19

Application for plugging filed 4-17-48 19

Application for plugging approved 4-19-48 19

Plugging commenced 5-10-48 19

Plugging completed 6-2-48 19

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Rives

Producing formation None Depth to top Bottom Total Depth of Well 3483' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Rotary Hole (none detected)				8 5/8 5 1/2	276' 3483'	none 2853'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Plugged back to top of Kansas city perforations at 3374' ran 5 sks cement
Filled hole with heavy mud to 250' set bridge and run 15 sks cement
Mud to 25' set bridge and filled with cement to top.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Jones, Shelburne & Farmer, Inc. 6-9-48
Address Russell, Kansas

STATE OF Kansas COUNTY OF Russell, ss.

John O. Farmer (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God.


(Signature) John O. Farmer

Russell Kans (Address)

SUBSCRIBED AND SWORN to before me this 7th day of May 1948

My commission expires January 5-1952
Notary Public.

22-237 7-47-10M



15-163-02512-00-00

CONTRACTOR'S VERIFIED LOG

Operator Jones, Shelburne & Farnes, Inc. Farm Name Peterson Well No. 1
 Location W 1/2 SE 1/4 Sec. 16 T 8 R 19W.
 Pool Name Silvers County Rooks State Kansas
 Commencement Date 1-7-48 Completion Date 1-21-48

LOG OF WELL

Depth		Formation	Deviation from Vertical (Degrees)	Remarks
From	To			
0	50	Surface formation		
50	235	Shale + Shells		
235	550	Shale		
550	700	Shale shells		
700	750	Sand		
750	980	Shale + sand		
980	1170	Sand		
1170	1200	Red Rock		
1200	1350	Shale + sand		
1350	1470	Red Rock + sand		
1470	1515	Anhydrite		
1515	1870	Shale + shells		
1870	2148	Shale + Lime		
2148	2206	Lime + Shale		
2206	2318	Shale + Lime		
2318	2328	Lime + Shale		
2328	2373	Lime		
2373	2490	Lime + Shale		
2490	2620	Shale + Lime		
2620	2700	Lime + Shale		
2700	2875	Shale + Shells		
2875	3022	Shale + Lime		
3022	3082	Lime		
3082	3162	Lime + Shale		
3162	3235	Shale + Lime		
3235	3333	Lime + Shale		
3333	3400	Lime		
3400	3445	Lime + Shale		
3445	3476	T D. rotary		
3476	3483	Cable Tool T.D.		

APR 17 1948

4-19-48

PLUGGING
 FILE SEC 16 T 8 R 19W
 BOOK PAGE 23 LINE 22