


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

15-163-02537-00-00

Rocks _____ County, Sec. 16 Twp. 8 Rge. 19 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NE NE SW
Lease Owner National Associated Petroleum Co.
Lease Name Katherine Petersen Well No. 1
Office Address 5th Floor - Ritz Bldg., Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 20 19 57
Application for plugging filed June 20 19 57
Application for plugging approved June 20 19 57
Plugging commenced June 20 19 57
Plugging completed June 20 19 57
Reason for abandonment of well or producing formation no oil in commercial quantities found
If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3565 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	213'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with extra heavy rotary mud from total depth to 540'. Set Plug #1 at 540' with 1/2 sacks Hulls and bridged with rocks cemented with 30 sacks cement. Filled hole with extra heavy rotary mud from Plug #1 to 40'. Set Plug #2 at 40' cemented with 1 sack Hulls and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Prime Drilling Company
Address 814 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF Sedgwick, ss. R. R. McNicol (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. R. McNicol
814 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of June, 19 57

My commission expires September 30, 1959

Darlene May Notary Public.
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC. 16 T. 8 R. 19
BOOK PAGE 22 LINE 22

JUN 27 1957
CONSERVATION DIVISION
Wichita, Kansas
6-25-57

15-163-02537-00-00

ROTARY DRILLING LOG

OPERATOR: National Associated Petroleum Co.
Katherine Petersen #1
NE NE SW Sec. 16-8-19W,
Rooks County, Kansas

CONTRACTOR: Prime Drilling Company
COMM: 6/7/57
COMP: 6/20/57

Remarks: Set 8-5/8" surface casing
at 213' cemented with 185 sacks Pozmix
2% C.C.

Formations:

Surface clay & Post Rock	105'
Pyrite shale & Rock	175'
Shale & Shells	640'
Shale & Sand Breaks	805'
Shale & Shell & Lime Breaks	940'
Sand	1165'
Red Bed, Shale & Sand	1445'
Anhydrite	1480'
Shale & Shells	1920'
Shale & Lime	2920'
Lime	3425'
Lime & Shale	3495'
Cherty Lime & Shale	3508'
Arbuckle	3525'
Dolomite	3565'
Rotary Total Depth (D&A)	3565'

We Certify the above log is true and
correct to the best of our knowledge
and belief.

PRIME DRILLING COMPANY

R. R. McNicol
R. R. McNicol

6-25-57

PLUGGING			
FILE	SEC	T	R
	16	8	19W
BOOK	PAGE	LINE	
	22	22	