


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

15-163-60202-00-00
WELL PLUGGING RECORD

Rooks County, Sec. 20 Twp. 8S Rge. 19 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SE SE
Lease Owner Anderson-Prichard Oil Corporation
Lease Name Veverka "B" Well No. 1
Office Address Box 142 - Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 4, 19 49
Application for plugging filed August 4, (Verbal) 19 49
Application for plugging approved August 4, (Verbal) 19 49
Plugging commenced August 4, 19 49
Plugging completed August 4, 19 49
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well 3512 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	152	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled to 152' with Heavy Mud
Set Plug at 152'
20 sax cement on top of plug
Filled with heavy mud to 30' from top
Set top plug at 30', then 10 sax cement on plug
Tied top plug with wire

RECEIVED
AUG 17 1949
STATE CORPORATION COMMISSION
KANSAS


(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Anderson-Prichard Oil Corporation
Address Box 142 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, SS.
Gerald M. Dougherty (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gerald M. Dougherty
Box 142 - Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 16 day of August 19 49
Charles M. Davis
Notary Public.

SEP 17 1952



15-163-00202-00-00

WELL LOG

BEN F. BRACK OIL COMPANY, INC.
309-10 Brown Building
Wichita, Kansas

Anderson-Prichard Oil Corporation

No. 1 Veverka "B"
SW/4 SE/4 SE/4,
20-8S-19W, Rooks
County, Kansas

Comm: 7-20-49
Comp: 8-4-49
Total Depth: 3512'

cellar	5
surface soil, shells	151
surface soil, shells, shale	300
shale & shells	450
shale - shells	690
shale-sand-streaks	945
sand	1130
sand & red bed	1435
anhydrite	1475
shale & shells	1710
salt-shale	1840
shale-lime-shells	1930
shale & lime	2025
lime & shale	2150
lime-shale	2270
lime & shale	2330
shale & broken lime	2435
lime-shale	2550
lime & shale	2635
shale & lime	2695
shale-lime	2815
shale & lime	2915
lime & shale	2990
lime-shale	3065
lime & shale	3150
lime	3185
lime	3215
lime	3235
lime	3275
lime	3310
lime	3335
lime	3375
lime	3390
lime	3410
lime	3460
lime & conglomerate	3480
lime	3487
lime, Arbuckle	3487
lime	3512

TOTAL DEPTH: 3512

8/17/49
RECEIVED
AUG 17 1949
ANDERSON-PRICHARD OIL CORPORATION
WICHITA, KANSAS

To the best of my knowledge the above is a true and correct record of the formations and depths at which found.

BEN F. BRACK OIL COMPANY, INC.

By *Ben F. Brack*

WITNESS: *Lucille S. Plann*

DATE: *Aug 5-49*

INDEXED 20 8 1949
FILED 108 40