

15-163-20120-00-00


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County, Sec. 20 Twp. 8S Rge. (H)/19 (W)

Location as "NE/CNW/SW" or footage from lines NW SW SW
Lease Owner Prospect Oil, Inc.
Lease Name LOWRY Well No. 1
Office Address 811 Union Center; Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 26, 19 68
Application for plugging filed (verbally) August 26, 19 68
Application for plugging approved " August 26, 19 68
Plugging commenced August 26, 19 68
Plugging completed August 26, 19 68
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3445 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	243'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set 1st plug @715' w/100 sx. cement;
Set 2nd plug @245' w/20 sx. cement;
Set top plug @ 40' w/10 sx. cement.
Job completed 2:15 p.m., 8-26-68.

RECEIVED
STATE CORPORATION COMMISSION
AUG 29 1968
CONSERVATION DIVISION
Wichita, Kansas

8/27/68

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.
Address 801 Union Center; Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
A. L. Abercrombie (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. L. Abercrombie

801 Union Center; Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of August, 19 68.

My commission expires July 15, 1972

Sue J. Blunck
Sue J. Blunck Notary Public.

15-163-20120-00-00

CONTRACTOR'S WELL LOG

OWNER:	Prospect Oil, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
LEASE NAME:	#1 LOWRY
LOCATION:	NW SW SW, Sec. 20-8S-19W Rooks County, Kansas
GEOLOGIST:	Jack Wharton
COMMENCED:	August 19, 1968
COMPLETED:	August 26, 1968

0	253	Rock & Shale
253	490	Shale & Shells
490	760	Dakota Sand
760	875	Shale
875	1170	Cedar Hills Sand
1170	1444	Red Bed & Sand Streaks
1444	1482	Anhydrite
1482	1689	Shale & Shells
1689	1975	Shale
1975	1995	Lime & Shale
1995	2205	Shale
2205	3070	Lime & Shale
3070	3200	Lime
3200	3240	Lime & Shale
3240	3445	Lime
	3445	Rotary Total Depth

Drilled 250' of 12-1/4" surface hole and set 8-5/8" csg. @243' w/150 sx.
 cement cement. Cement circulated and plug was down August 19, 1968.
 Dev & Abandonment

FORMATION	SAMPLE TOPS	ELEVATION	
Anhydrite	1444	(+ 536)	1980 K. B.
Peper	2934	(- 954)	1978 D. F.
Wabner	3135	(-1155)	1972 G. L.
Loronto	3156	(-1176)	
Lansing	3174	(-1194)	
S. K. C.	3384	(-1404)	
Arbuckle	3433	(-1453)	
Rotary Depth	3445	(-1465)	

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 29 1968
 CONSERVATION DIVISION
 Wichita, Kansas
 8/29/68

STATE OF KANSAS)
) SS
 COUNTY OF ROKESBORO)

I, Jack Wharton, of Abercrombie Drilling, Inc., hereby declare that the above and foregoing is a true copy of the log of the #1 LOWRY, NW SW SW, Sec. 20-8S-19W, Rooks County, Kansas, as reflected by the files of Abercrombie Drilling, Inc.

A. L. Abercrombie
 President

I, Sue J. Blunck, a Notary Public, in and for the State of Kansas, do hereby certify that the above is a true copy of this 28th day of August, 1968.

Sue J. Blunck
 Notary Public