

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-163-20280-05 - 02 Form CP-4


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Rooks County, Sec. 20 Twp. 8S Rge. (E) 19 (W)

Location as "NE/CNW/SW" or footage from lines E/2 NE SE
Lease Owner Abercrombie Drilling, Inc.
Lease Name VEVERKA "B" Well No. 1
Office Address 801 Union Center; Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 22, 19 69
Application for plugging filed (verbally) December 21, 19 69
Application for plugging approved (verbally) December 21, 19 69
Plugging commenced December 21, 19 69
Plugging completed December 22, 19 69
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3485 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	263'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set 1st plug @720' w/50 sx. cement;
Set 2nd plug @240' w/20 sx. cement;
Set top plug @ 40' w/10 sx. cement.
Job was completed at 2:00 a.m., 12-22-69.

RECEIVED
STATE CORPORATION COMMISSION
DEC 31 1969
CONSERVATION DIVISION
Wichita, Kansas

12/31/69

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.
Address (office) 801 Union Center; Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Jerry A. Langrehr (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jerry A. Langrehr
Jerry A. Langrehr
801 Union Center; Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of December, 19 69.

My commission expires November 12, 1973

Sue J. McCoy
Sue J. McCoy,
Notary Public.

15-163-20280-00-00

CONTRACTOR'S WELL LOG

OPERATOR: Abercrombie Drilling, Inc.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Veverka "B" #1
 LOCATION: E/2 NE SE, Sec. 20-8S-19W
 Rooks County, Kansas
 GEOLOGIST: Jack K. Wharton
 DATE COMMENCED: December 14, 1969
 DATE COMPLETED: December 22, 1969

0	40	Rock
40	85	Clay
85	130	Sand & Shale
130	510	Shale
510	765	Sand
765	925	Shale & Sand Stringers
925	1175	Sand
1175	1441	Shale
1441	1488	Anhydrite
1488	1730	Shale
1730	2490	Shale & Lime
2490	2623	Lime & Shale
2623	2810	Lime
2810	2967	Lime & Shale
2967	3335	Lime
3335	3378	Lime & Chert
3378	3443	Lime & Shale
3443	3485	Lime
	3485	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 31 1969
 CONSERVATION DIVISION
 Wichita, Kansas
 12/31/69

Drilled 268' of 12-1/4" surface hole and set 8-5/8" surface casing @263' w/150 sx. Sunset cement. Cement circulated. Plug was down 8:30 p.m., 12-14-69. Dry & Abandoned.

ELECTRIC LOG TOPS

ELEVATION:

Heebner	3158	(-1149)	2009 K.B.
Toronto	3180	(-1171)	2007 D.F.
Lansing	3197	(-1188)	2001 G.L.
Arbuckle	3447	(-1438)	
E.L.T.D.	3485	(-1476)	

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jerry A. Langrehr, president of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and complete log of the Veverka "B" #1, E/2 NE SE, Sec. 20-8S-19W, Rooks County, Kansas.

Jerry A. Langrehr
 Jerry A. Langrehr

Sworn to before me, a Notary Public, in and for the above named county and state, as of this 30th day of December, 1969.

Sue J. McCoy
 Sue J. McCoy, Notary Public

My Commission Expires: November 12, 1973