

P

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
OCT 28 1977  
10-28-77  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -163 -20,749 -00-00 (of this well)

Operator's Full Name Murfin Drilling Co.

Complete Address 617 Union Center, Wichita, Kansas

Lease Name Dechant Well No. 2

Location 1200' FSL & 440' FWL of NE/4 APP W/2 W/4 NE/4 Sec. 26 Twp. 8 Rge. (E) (W) 18

County Rooks Total Depth 3487'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor        Co. Tools       

Address        License No.       

Operation Completed: Hour 11:30 P Day 26 Month 10 Year 1977

The above well was plugged as follows:  
RTD 3487' 8 5/8 csg set 172' cwc 150 sk. Plg. Mat. 50-50 poz 6% total gel.  
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 550' thru drill pipe.  
Heavy mud to 160' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid  
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**  
DATE 10-28-77  
INV. NO. 611-4

Signed: Leo Massey  
Well Plugging Supervisor