

15-163-01419-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 92-37

LOCATION NE NW SE

SEC. 33 TWP. 8 RGE. 19

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 5 Lease Fidelis

Operator Phillips Pet Co Address Box 779 Great Bend, Kans

Field _____ County Rooks

Total Depth 3422 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. _____

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 1431' circulated with cement - 5 1/2" at 3416' with
200 sax cement behind - Lane Wells plugs to 3166' - perforated
3166'.

Sand to 3140', set 4 sax cement with dump bailer - pulled 2325'
5 1/2" - mud to 200' (25 sax commercial mud) set rock at 200' with
15 sax cement, mud to 35', set rock and 10 sax cement to bottom
cellar.



District Conservation Agent

Date 9-24-56

PLUGGING
FILE SEC. 33 T. 8 R. 19W
BOOK PAGE 92 LINE 37

9/27/56