

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-20088-00-00

RECEIVED
STATE CORPORATION COMMISSION
JAN 10 1969
CONSERVATION DIVISION
Wichita, Kansas
1-10-69

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Clinton Oil Company

Complete Address: 6810 West Hi - way 54 Wichita, Kansas 67209

Lease Name Kriley Well No. 1 - V

Location CE/2 NW SW Sec. 26 Twp. 8 Rge. 18 (E) (W) XX

County Rooks Total Depth 3518

Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 9:30A Day 8 Month 1 Year 1969

The Above well was plugged as follows:

Total Depth 3518' 8 5/8 csg set at 203' cwc 175 sk.

5 1/2 csg set at 3440' cw 125 sk cmt.

5 1/2 csg PBSD 3406' with top perf. 3361'.

Filled 5 1/2 csg W/sd (3350-3406) Dumped 5 sk cmt W/dump bailer. (3310-3350)

Cutoff and recov. 2830' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 400 lbs hulls, 24 sk gel, 140 sk 50-50 poz cmt.

W/6% gel, 4 sk gel, 100 lbs hulls, plug and 10 sc cmt. Max. 400 lbs. SI 400 lbs.

Cmt. (0-40) gel (40-200) Cmt (200-720) Gel (720-TD)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Massey
Well Plugging Supervisor

DATE 1/10/69
INV. NO. 9171-W