

KANSAS

Form CP-3  
Rev. 6-26-62

*Y* STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

15-163-20311-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 8 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
6-8-70

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Beacon Resources Corporation

Complete Address: 1000 Century Plaza, Wichita, Kansas

Lease Name Kriley Well No. 1

Location SE SW SW Sec. 26 Twp. 8 Rge. (E) (W) 18

County Rooks Total Depth 3490

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated:     

Plugging Contractor: B & B Drlg.

Address: Wichita, Kansas License No.     

Operation Completed: Hour 11 P Day 6 Month 6 Year 1970

The Above well was plugged as follows:

RTD 3490' 8 5/8 csg set at 230' cwc Cmt. Mat. 100 Sk reg poz W/6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

I hereby certify that the above well was plugged as herein stated.

Signed: Geo F. Massey  
Well Plugging Supervisor

INVOICED

DATE 6/8/70

INV. NO. 2018-W