

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-00596-00-08

RECEIVED
STATE CORPORATION COMMISSION

JUL 28 1962

CONSERVATION DIVISION
Wichita, Kansas

7-23-62

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name John P. Jennings
Complete Address: c/o Raymond Oil Co 410 4th Natl Bk Bldg Wichita, Kans
Lease Name Kenyon Well No. 1
Location NE SE SE Sec. 5 Twp. 8 Rge. (E) (W) 21
County Graham Total Depth 3620
Abandoned Oil Well x Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Bert Self
Address: Hutchinson, Kansas License No. 48
Operation Completed: Hour Noon Day 17 Month 7 Year 62

The Above well was plugged as follows:

8 5/8" 176' circulated with cement - 5 1/2" 3560' with 125 sax cement.
Sand to 3540', set 4 sax cement with dump bailer - pulled 2900' 5 1/2" to
550', circulated hole with heavy mud through 5 1/2" at 550' (25 sax Gel),
displaced 20 sax cement through 5 1/2" at 550', heavy mud to 180', set 20
sax cement at 180', heavy mud to 35', set bridge and filled to 0' with cement
Mudding and cementing by Halliburton Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 7/23/62

INV. NO. 5413-W