

KANSAS

M

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20225-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAY 26 1969
CONSERVATION DIVISION
Wichita, Kansas

5-26-69

Operator's Full Name Robert R. Price and Aspen Drilling Company,

Complete Address P. O. Box #783, Great Bend, Kansas.

Lease Name Kansas Children's Home Well No. 1

Location NE-SW-NE Sec. 16 Twp. 8 Rge. (E) (W) 21

County Graham Total Depth 3545'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Aspen Drilling Company,

Address Box #783, Great Bend, Kansas. License No.

Operation Completed: Hour 9:00 PM Day 17 Month 5 Year 1969

The above well was plugged as follows:

237'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 525'.

Circulated hole with heavy mud. Pulled DP to 750' and displaced 100 Sx. cement thru
DP from 750' to 425'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from 240'
to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *A. L. Pichol*
Well Plugging Supervisor

DATE 5/27/69
INV. NO. 9820-W