

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-163-20500-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 4 1973  
CONSERVATION DIVISION  
Wichita, Kansas  
9-4-73

Operator's Full Name Pate-Dombaugh & Martin Explorations

Complete Address 502 Union Center, Wichita, Kansas

Lease Name Kriley Well No. 1

Location SW NW SE Sec. 22 Twp. 8 Rge. (E) (W) 18

County Rooks Total Depth 3400'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated     

Plugging Contractor Dreiling Oil Co.

Address Vixtoria, Kansas License No.     

Operation Completed: Hour 5:45 A Day 30 Month 8 Year 1973

The above well was plugged as follows:  
RTD 3400' 8 5/8 csg set at 207' cwc. Cmt. Mat. 50-50 poz cmt W/6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Massey  
Well Plugging Supervisor

DATE 9-4-73

INV. NO. 7868-W