

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 142-28
LOCATION SE SE NE
SEC. 24 TWP. 8 RGE. 18 W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Thomas
Operator Jones, Shelburne & Farmer, Inc. Address Russell, Kans
Field _____ County Rooks
Total Depth 3430 Feet.
Plugging Contractor Forbes Casing Pulling
Plugging Contractor's License No. 49
Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 158' circulated with cement. 5 1/2" at 3425', squeezed at 700',
P.B. to 3329', perforated at 3315' - filled with sand to 3310',
set 4 sax cement with dump bailer, pulled 530' 5 1/2", pumped hole
full commercial mud (25 sax Gel), pumped cementing plug to 250'
followed by 80 sax cement - cement 250' to 0'.

Mudding and cementing by Globe Cementing Co. (300# pump pressure)

Edward Petty
District Conservation Agent

Date 2-17-57

PLUGGING
FILE SEC 24 T. 8 R. 18 W
BOOK PAGE 142 LI. E. 28

RECEIVED
STATE CORPORATION COMMISSION

FEB 25 1957
Feb 25, 1957
CONSERVATION DIVISION
Wichita, Kansas