

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

FEB 5 1975
Feb 5th, 1975
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name John O. Farmer, Inc.

Complete Address Box 352, Russell, Kansas 67665

Lease Name Pearl Well No. 2

Location SE NE SE Sec. 24 Twp. 8 Rge. (E) (W) 18

County Rooks Total Depth 3426'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering, Inc.

Address Box 698, Great Bend, Kansas 67530 License No. 670

Operation Completed: Hour 2:30 P Day 1 Month 2 Year 1975

The above well was plugged as follows:

- Total Depth 3426' 8 5/8 csg set at 170' cwc 100 sk.
- 5 1/2 csg set at 3407' cw 75 sk cmt. with top perf. (3136)
- Filled 5 1/2 csg with sand to 3100' -dumped 5 sk cmt W/dump bailer. (3100-3065)
- Cutoff & recovered A/1000' of 5 1/2 csg.
- Mixed & pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls -70 sk
- 50-50 poz cem 6% total gel--10 sk gel & water--released plug & 50 sk 50-50 poz cmt 6% total gel.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Z. Massey
Well Plugging Supervisor

DATE 2/5/75
INV. NO. 779-W