

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 38-13

LOCATION NE NE SE

SEC. 32 TWP. 8 RGE. 18

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Carmichael

Operator H. Gore Address Wichita, Kans

Field _____ County Rooks

Total Depth 3510 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 180' circulated with cement - 5 1/2" at 3456

with 100 sax cement behind.

Filled with sand to 3450', set 5 sax cement with dump

bailer, pulled 2900' 5 1/2", filled hole with mud to

175' set rock bridge and 15 sax cement, filled with

mud to 40', set rock bridge and 10 sax cement to bottom

cellar .

RECEIVED
STATE CORPORATION COMMISSION

OCT 31 1950

CONSERVATION DIVISION
Wichita, Kansas

District Conservation Agent

Date 10-29-50

PLUGGING
FILE SEC 32 T 8 R 18
PAGE 38 LINE 13