

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
 Conservation Division
 800 Bitting Building
 Wichita, Kansas

FILE NO. _____

LOCATION SE SW SE

SEC. 31 TWP. 8 RGE. 18 W

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Andreason

Operator Derby Drg Co Address Wichita, Kans

Field _____ County Rooks

Total Depth 5494 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 157' circulated with cement - 5 1/2" at 5480'
Cement and Lane Wells plugs to 5310', chat and mud to 5200',
5 sax cement at 5200', with dump bailer, pulled 2800' 5 1/2"
casing, mudded hole to 157', wood plug and 15 sax cement,
heavy mud to 55', wood plug, rock and 10 sax cement, to
bottom cellar,

RECEIVED

OCT 12 1949
 OCT 12 1949

[Signature]
 District Conservation Agent

Date 10-11-49

FILE NO. 31 8 186
 BOOK PAGE 119 LINE 17

+