


15-163-00694-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. 32 Twp. 8S Rge. 18W (X) (W)
Location as "NE/CNW/SW" or footage from lines NE NE SW
Lease Owner Fred B. Anschutz
Lease Name Thompson-Carmichael Well No. 1
Office Address Union National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1-18 1954
Application for plugging filed 1-18 1954
Application for plugging approved 1-18 1954
Plugging commenced 1-18 1954
Plugging completed 1-18 1954
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3597' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	211'	----

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Top plug set at 40' with 10 sacks cement
Bottom plug set at 200' with 15 sacks cement

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Anschutz Drilling Co., Inc. JAN 22, 1954
Address Union National Bank Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
E. G. Koelling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. G. Koelling
Union Nat'l Bk Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of January, 19 54

My commission expires May 2, 1956

Jeaneline Duman
Notary Public.

24-7368-5 3-53-20M
PLUGGING
FILE SEC 32 T 8 R 18W
BOOK PAGE 8 LINE 13

DRILLER'S LOG

FRED B. ANSCHUTZ
 #1 Thompson-Carmichael
 NE NE SW - 32-8S-18W
 Rooks County, Kansas

<u>FROM</u>	<u>TO</u>	
0	25	Surface clay
25	170	Shale & shells
170	190	Sand
190	217	Shale & shells
217	700	Shale & sand streaks
700	950	Shale & shells
950	1180	Sand
1180	1460	Red rock
1460	1495	Anhydrite
1495	1775	Shale & shells
1775	1975	Shells, shale & lime
1975	2060	Shale & shells
2060	2325	Lime & shale
2325	2410	Lime
2410	2540	Lime, shale & sand
2540	3002	Lime & shale
3002	3165	Lime
3165	3252	Lime & shale
3252	3478	Lime
3478	3508	Shale & lime
3508	3579	Conglomerate
3579	3597	Arbuckle
		ROTARY TOTAL DEPTH
		D&A

COMMENCED: 1-7-54
 COMPLETED: 1-18-54

CASING RECORD

Set 8-5/8" surface casing at 211'
 with 125 sacks cement.

ELEVATION: 2051 RB

TOPS: (RB)

Anhydrite 1460
 Heebner 3206
 Toronto 3225
 Lansing 3246
 Conglomerate 3508
 Arbuckle 3572

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the #1 Thompson-Carmichael located NE NE SW Section 32-8S-18W, Rooks County, Kansas.

ANSCHUTZ DRILLING COMPANY, INC.

BY: *E. G. Koelling*
 E. G. Koelling

Subscribed and sworn to before me this 21st day of January, 1954.

My Commission Expires: May 2, 1956.

Jacqueline Lennan
 Notary Public

JAN 22 1954

