


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Rooks County, Sec. 32 Twp. 8 Rge. 18W (E) (W)

Location as "NE/CNW%SW%" or footage from lines SW SE NE  
Lease Owner The Carl Todd Drilling Company, etal  
Lease Name Welch Well No. 1  
Office Address 706 Union Center, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 11-14 19 56  
Application for plugging filed 11-14 19 56  
Application for plugging approved 11-14 19 56  
Plugging commenced 11-14 19 56  
Plugging completed 11-14 19 56  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Depth to top Bottom Total Depth of Well 3520 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	LOG ATTACHED					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set plug at 190' cemented with 1/2 sax hulls and 20 sax cement,  
set plug at 35' cemented to bottom of cellar with 1/2 sax hulls,  
10 sax cement

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 29 1956  
NO.  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor company tools  
Address

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Carl Todd (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Carl Todd  
706 Union Center, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of November, 19 56

March Long  
Notary Public.

My commission expires December 14, 1957

PLUGGING  
SEC 32 T. 8 R. 18.W  
BOOK PAGE 117 LINE 1

THE CARL TODD DRILLING COMPANY  
706 Union Center  
Wichita, Kansas

#1 Welch  
SW SE NE Sec. 32-8S-18W  
Rooks County, Kansas

COMMENCED: November 5, 1956  
COMPLETED: November 14, 1956

ELEVATION: 2047 K. B.

CASING RECORD

0 - 125	Shale	8-5/8" spiral weld casing set at 200'	
125 - 200	Shale and shells	cemented with 150 sacks cement,	
200 - 400	Shale	3 sacks CC	
400 - 580	Shale		
580 - 780	Shale, sand		
780 - 840	Sand		
840 - 940	Shale, shells		
940 - 1200	Sand, shale		
1200 - 1405	Red Bed, shale, shells		
1405 - 1450	Shale, shells		
1450 - 1490	Anhydrite		
1490 - 1690	Shale, shells		
1690 - 1900	Shale, shells, salt		
1900 - 2050	Shale, lime		
2050 - 2160	Lime, shale		
2160 - 2285	Lime, shale		
2285 - 2395	Lime, broken		
2395 - 2565	Lime, shale		
2565 - 2645	Lime		
2645 - 2810	Shale, lime		
2810 - 2940	Lime, shale		
2940 - 3005	Lime		
3005 - 3090	Lime, shale		
3090 - 3278	Lime		
3278 - 3345	Lime		
3345 - 3380	Lime, chert		
3380 - 3438	Lime		
3438 - 3489	Cong.		
3489 - 3520	Arbuckle		
3520	Rotary Total Depth		

TOPS

Topeka	2977
Heebner	3191
Toronto	3211
Lansing	3231
Arbuckle	3489
DST #1, 3198-3278, open 1 hr., rec. 26' mud slightly oil specked, BHP 960	
DST #2, 3278-3315, open 30 min., rec. 10' mud, BHP 0	
DST #3, 3482-95, open 1 hr., rec. 7' mud, BHP 0	

I hereby certify that the above is a true and correct log, to the best of my knowledge and belief.

THE CARL TODD DRILLING COMPANY

By: *Carl Todd*

**RECEIVED**  
STATE CORPORATION COMMISSION

NOV 29 1956  
NOV 29 1956  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC. 32 T. 8 R. 18W  
BOOK PAGE 117 LINE 1