

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217

Rooks County, Sec. 33 Twp. 8 Rge. 18 (E) 18 (W)

Location as "NE/CNWSW" or footage from lines NE NW SW
Lease Owner Petroleum, Inc.
Lease Name Carmichael Well No. 1-1
Office Address RR #2, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced May 1 1974
Plugging completed May 8 1974
Reason for abandonment of well or producing formation depleted



Locate well correctly on above
Section Plot

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3431 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|-------|--------|--------|------------|
| | | 0 | 200' | 8 5/8" | 200' | none |
| | | | 3431' | 5 1/2" | 3431' | 632.20 |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 3000' and dumped 4 sacks of cement.

Plugged well with 5 sacks of hulls, 25 sacks of mud and 100 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 14 1974
MAY 14 1974
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor PIPE PULLERS, INC.
Address Box 486, Ellinwood, Kansas 67526

STATE OF KANSAS COUNTY OF BARTON, ss.
Evelyn Roth (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of May 1974

My commission expires Feb. 10, 1975

George A. Meyer
Notary Public.


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- GARVEY DRILLING COMPANY
Farm- Mcsherr-Carmichael No. 1

SEC. 33 T. 8 R. 18W
NE NW SW

Total Depth. 3440
Comm. 12-9-54 Comp. 12-19-54
Shot or Treated.
Contractor. Nye & Snell Drlg. Co.
Issued. 3-12-55

County Rooks KANSAS



Elevation. 1998 DF

Production. Phy. Pot. 474 BOPD

CASING:

8 5/8" 200'
5 1/2" 3431'

Figures indicate Bottom of Formations.

| | |
|----------------------|----------|
| shale & shells | 990 |
| sand | 1140 |
| redbed | 1392 |
| Anhydrite | 1440 |
| shale, shell & salt | 1690 |
| shale, lime & shells | 2020 |
| shale & lime | 3200 |
| lime | 3222 |
| lime & shale | 3268 |
| lime | 3420 |
| shale & lime | 3432 RTD |
| lime | 3440 |
| Total depth | |

| | |
|-------------|------|
| Scout Tops: | |
| Heebner | 3132 |
| Toronto | 3154 |
| Lansing | 3175 |
| Arbuckle | 3429 |

RECEIVED
STATE CORPORATION COMMISSION
MAY 17 1974
MAY 17 1974
CONSERVATION DIVISION
Wichita, Kansas