

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-163-03018-00-00

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

12/3/62

Operator's Full Name Frank Black

Complete Address: 600 W Washington Mc Pherson, Kansas

Lease Name Dopita Well No. 2

Location CNW SE Sec. 31 Twp. 8 Rge. (E) (W) 17

County Rooks Total Depth 3429

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pilling Co

Address: Chase, Kansas License No. 436

Operation Completed: Hour 4PM Day 29 Month 11 Year 62

The Above well was plugged as follows:

8 5/8" 152 circulated with cement - 5 1/2" 3386' with 100 sax cement -
hole in 5 1/2" - 4 1/2" liner set at 804' circulated in with cement to 0'
tried to drill hole out - unable to do so - tools went out of hole
below 4 1/2" liner.

Pumped hole full heavy mud (35 sax Gal) followed by 60 sax cement
at 350# pump pressure - no pipe recovery possible.

Mudding and cementing by Knight Company pump truck.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 12/4/62
INV. NO. 6136-W

Signed: [Signature]
Well Plugging Supervisor